

15-077-00058-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper

County. Sec. 3 Twp. 32 Rge. 9 (E) 9 (W)

Location as "NE/CNW/SW" or footage from lines SE NE NW

Lease Owner Earl F. Wakefield Etal.

Lease Name Dusenbury Well No. 1

Office Address 515 Union Center Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil & Gas Well

Date well completed 7/16/54 19

Application for plugging filed 10/20/57 19

Application for plugging approved 10/29/57 19


Plugging commenced 12/5/57 19

Plugging completed 12/15/57 19

Reason for abandonment of well or producing formation Not economical

If a producing well is abandoned, date of last production 2/15/55 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4525 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	200	None
				5 1/2"	4525	3545

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dump 10 sx. cement 4525 to 4465

Dump 4 sx. cement 4465 to 4455

Pump in & circulate 60 sx. aqua jel, set bridge at 200 ft., plugged with rock & cement to 125 ft., plugged with mud to 40 ft., Cement & rock to top of surface pipe.

RECEIVED
STATE CORPORATION COMMISSION

DEC 27 1957
12-27-57
CONSERVATION DIVISION

Name of Plugging Contractor Earl F. Wakefield (If additional description is necessary, use BACK of this sheet)

Address 515 Union Center Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Earl F. Wakefield

~~Employee~~ (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl F. Wakefield
515 Union Center Bldg., Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of December, 19 57

My commission expires July 26, 1958

C. A. Snow
Notary Public.

PLUGGING
FILE SEC 3 T 32 R 94
BOOK PAGE 57 LINE 32

Dusenbury #1
 Owner: Earl F. Wakefield, etal
 Contractor: Earl F. Wakefield
 Comm: 6/14/54 Comp: 7/1/54

SE NE NW
 3-32S-9W
 Harper County, Kansas
 Casing: 200' of 8 5/8"
 4525' of 5 1/2"

Elevation: 1623 D. F.

Surface	200
Red Bed	250
Red Rock	355
Red Rock and Shale	850
Shale and Shells	1525
Lime	1665
Lime (Sandy)	1780
Lime and Shale	1965
Lime (Sandy)	2000
Lime and Shale	2280
Lime	2350
Lime and Shale	2525
Lime and Sandy Shale	2625
Sandy Lime and Shale	2790
Shale and Lime	2920
Lime	3170
Lime (Broken)	3275
Lime	3355
Shale and Lime	3367
Lime	3465
Lime and Shale	3525
Lime with shale streaks	3575
(top of Douglas sand 3565)	
Sand and Shale	3678
Lime (Kansas City)	3965
Lime and Shale	4070
Lime	4255
Lime and Shale	4326
Sandy Lime	4333
Lime and Shale	4432
Lime and Chat (Mississippi)	4450
Chat	4525
Total Rotary Depth	4525

4432
 1623

 2809

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

10-29-57
 WICHITA DIVISION

I hereby agree and certify that the above is a true and correct copy of the log drilled on the Dusenbury #1 well located SE NE NW 3-32S-9W, Harper County, Kansas.

Earl F. Wakefield

Subscribed and sworn to before me this 14th day of July, 1954.

Hilda A. Boyd
 Notary Public

My commission expires Jan. 6, 1958

PLUGGING
 FILE SEC. 3 T. 32 R. 9W
 BOOK PAGE 57 LINE 32