

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH

X			

Locate well correctly on above  
Section Plat

Barber County, Sec. 32 Twp. 32S Rge. 15W (E) (W)  
 Location as "NE/CNWxSWx" or footage from lines SW-NW-NE  
 Lease Owner Sunray DX Oil Company  
 Lease Name Vaughn DeGeer Well No. 1  
 Office Address 300 Union National Bldg. Wichita, Kansas  
 Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
 Date well completed 7-7 19 65  
 Application for plugging filed 7-7 19 65  
 Application for plugging approved 7-8 19 65  
 Plugging commenced 7-8 19 65  
 Plugging completed 7-8 19 65  
 Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving Box 248 Pratt, Kansas  
 Producing formation Depth to top Bottom Total Depth of Well 5425 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUR IN	PULLED OUT
				13 3/8	219	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled w/mud from 225' to 5425'  
 50 sacks cement at 225'  
 20 sacks cement at 40'  
 25 sacks cement to surface

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 15 1965

7-15-65

CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company  
 Address 1100 Bitting Bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

V. A. Tracy (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

V. A. Tracy  
 300 Union Nat'l Bldg. Wichita, Kansas  
 (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 1965

My commission expires March 28, 1969

Mae Resco  
 MAE RESCO Notary Public.

15-007-30374-0000

Sunray DX Oil Company  
Tulsa, Oklahoma

9 July 1965  
Wichita, Kansas

*Vance*

Drlg. Contractor: Stickle Drilling Co.  
Date Commenced: 17 June 1965  
Date Completed: 7 July 1965

Vaughn DeGeer #1  
SW NW NE 32-32S-15W  
Barber County, Kansas

DRILLER'S LOG

Depth figures indicate base of formation:

Shale	369
Shale and red bed	1141
Shale and shells	1925
Shale	2195
Lime	2405
Lime and shale	2740
Shale and lime	3200
Shale and lime stacks	3430
Shale and lime	3990
Lime and shale	4075
Lime	4869
Chert	4910
Cherty lime	4972
Lime	5065
Lime and shale	5105
Lime	5137
Lime and shale	5172
Lime	5195
Lime and chert	5268
Lime	5310
Lime and sand	5327
Sand and lime	5380
Sand and dolomite	5395
Arbuckle	5425

RECEIVED  
STATE CORPORATION COMMISSION

JUL 15 1965  
7-15-65  
CONSERVATION DIVISION  
Wichita, Kansas

I, C. W. Meyer, hereby certify that to the best of my knowledge and belief, the above is a true and complete Driller's Log of the Sunray DX Oil Company's Vaughn DeGeer #1, Ctr. SW NW NE 32-32S-15W, Barber County, Kansas.

*C. W. Meyer*

C. W. Meyer

*Wanda J. Steakley*  
Wanda J. Steakley, Notary Public

My Commission Expires 16 January 1966.