

15-007-21118-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barber SEC. 30 TWP. 32S RGE. 15W E/W  
Location as in quarters or footage from lines:  
1000' ENL. & 660' FWL

|  |  |  |  |
|--|--|--|--|
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |
|  |  |  |  |

Lease Owner Wells Energy Corp.  
Lease Name Brass Well No. 1  
Office Address 700 S. Colorado Blvd.-Suite 454, Denver, Co  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole 80222  
Date Well Completed March 2, 1981  
Application for plugging filed Verbal Application  
Plugging commenced March 2, 1981  
Plugging completed March 2, 1981  
Reason for abandonment of well or producing formation \_\_\_\_\_

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. V. Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4,766'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

| Formation | Content | From | To | Size   | Put in | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 513'   | None       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,766 ft. (rotary total depth) to 500 ft. Set plug at 500 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 500 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 10 sacks cement in rat hole and 5 sacks cement in mouse hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4½ inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services  
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.

Dean Britting, Agent (employee of owner) (owner) (operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting

251 N. Water-Suite 10, Wichita, KS  
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 18th day of March, 1981

Elsie Willison  
Elsie Willison - Notary Public.

My Commission expires: July 25, 1982

## KANSAS DRILLERS LOG

COMPANY Wells Energy Corp.

SEC. 30 T.32S R. 15W

FARM Brass

NO. 1

LOC. 1000' FNL &amp; 660' FWL

COUNTY Barber

ROTARY TOTAL DEPTH 4,766'

COMM. February 16, 1981 COMP. March 2, 1981

CONTRACTOR H-30, INC. (Rig #77)

ISSUED March 18, 1981

## CASING

10 3/4"

8 5/8" Set at 513' cemented w/450 sxs cement

ELEVATION 1,792' K.B.

5 1/2"

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

|                    |        |
|--------------------|--------|
| Red Bed            | 391'   |
| Red Bed and Shale  | 849'   |
| Red Bed            | 993'   |
| Shale              | 1,056' |
| Shale and Lime     | 2,141' |
| Lime and Shale     | 4,746' |
| Lime and Chert     | 4,766' |
| Rotary Total Depth | 4,766' |

I hereby certify the above and foregoing to be  
a true and correct log of the above described  
well as shown by the drilling reports.

H-30, INC.

  
Dean Britting

State of Kansas     )  
                          ) ss:  
County of Sedgwick )

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 18th day of  
March, 1981.

  
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982