

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-20939-0000

LEASE NAME Carr A

TYPE OR PRINT

WELL NUMBER #1

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

 Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR Raymond Oil Company, Inc.

SEC. 26 TWP. 32 RGE. 15 (E) or (W)

ADDRESS One Main Place, Suite 900 Wichita, KS 67201

COUNTY Barber

PHONE#(316) 267-4214 OPERATORS LICENSE NO. 5046

Date Well Completed 6-14-95

Character of Well Gas

Plugging Commenced 9-25-95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9-26-95

The plugging proposal was approved on 9-26-95 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filled? Yes If not, is well log attached?

Producing Formation Topeka Depth to Top 3563 Bottom 3573 T.D. 3650

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface	water	0	301	8 5/8	301	None
Topeka	gas	3563	3573	4 1/2	3648	2193

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
1st plug set CIBP at 3500' and dumped 2sx cement on top of CIHP, 2nd plug pumped down 8 5/8" surface pipe with 300lbs. hulls, 10sx gel, 50sx cement. Maximum pressure 400psi and shut in 100 psi. Used 65/35 Pozmix 6% gel by Halliburton. Recovered 2200' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Gressel Oil Field Service, Inc. License No. 3004

Address P.O. Box 438 Haysville, KS 67060

RECEIVED
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Raymond Oil Company, Inc.

STATE OF Kansas COUNTY OF Barber, ss.

OCT 18 1995

10-18-95

CONSERVATION DIVISION
Wichita, Kansas

Pat Raymond (Employee of Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Pat Raymond

(Address) P.O. Box 48788 Wichita, KS 67201

SUBSCRIBED AND SWORN TO before me this 17th day of October, 19 95

Sharon A. Hill
Notary Public

My Commission Expires:

