

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 16 Twp. 32S Rge. 15W (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW 7E

Lease Owner Time Petroleum Company

Lease Name Woods Well No. # 1

Office Address 815 Union National Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed May 13, 1962 19

Application for plugging filed July 2, 1962 19

Application for plugging approved July 2, 1962 19


Plugging commenced July 3, 1962 19

Plugging completed July 7, 1962 19

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hampton Prety Prie, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2	4862	4075
				3 5/8	270	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 10 sacks of cement to 4550 ft. shot pipe and pulled same out making 20 foot rock bridge at 290 ft. and dumped 20 sacks of cement filled with chunk mud to 35 ft, made 10 foot rock bridge and dumped 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

AUG 28 1962
8-28-62
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Smith & Smith Casing Pulling Co.
Address Box 8 Cushing, Oklahoma

STATE OF Kansas COUNTY OF Sedgewick, ss.
Bob J. Smith (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bob J. Smith
Box 8 Cushing, Okla (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 1962
Lorraine Shullcutt Notary Public.

Commission expires June 1, 1964

DRILLERS LOG

#1 Woods

SWS01NE

CASING RECORD:
263' of new 8-5/8"
surface casing

COMPANY: Time Petroleum Co.

DESCRIPTION: E/NW-NW-
Section 16-32-15W
Barber County, Kansas

TOTAL DEPTH:
4862'

COMMENCED: April 30, 1962

COMPLETED: May 13, 1962

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Gyp & Red Bed	0	535	Ran 263' of new 8-5/8" surface casing; set and cemented at 270' with 175 sacks of regular cement, 2% gel and 5 sacks of C. C. Plug down at 8:00 P. M. May 1, 1962.
Red Bed	535	1445	
Shale & Lime	1445	2115	
Lime	2115	2210	
Lime & Shale	2210	3900	
Shale & Sand	3900	3966	
Lime & Shale	3966	4262	
Lime	4262	4408	
Lime & Shale	4408	4492	
Lime	4492	4688	
Lime & Shale	4688	4760	
Lime	4760	4786	
Lime & Chert	4786	4842	
Lime	4842	4862	

Total Depth 4862'

Ran Welex Log.

Ran 155 Joints of 5 1/2" pipe; set and cemented at 4861' with 100 sacks of posmix with 18 lbs. salt per sack and 10% gilsonite. Plug down at 7:50 A. M. May 13, 1962.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Ralph Schuyler
Ralph Schuyler

Subscribed and sworn to before me this 14th day of May, 1962.

Elaine H. Taylor
Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1965

