

STATE OF KANSAS
STATE CORPORATION COMMISSION
209 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-115-20105 *0000*

LEASE NAME Haefner

WELL NUMBER 4

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2310 Aug. KCC
4950 Ft. from S Section Line

330 Ft. from E Section Line

LEASE OPERATOR Gear Petroleum Co. Inc.

SEC. 23 TWP. 17 RGE. 4E (E) ~~(E)~~

ADDRESS 125 N. Market Suite 1075 Wichita, Ks. 67202

COUNTY Marion

PHONE# (316) 265-3351 OPERATORS LICENSE NO. 5151

Date Well Completed ?

Character of Well oil

Plugging Commenced 9-4-91

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Plugging Completed 9-5-91

The plugging proposal was approved on 9-4-91 (date)

by Wichita, Ks. (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? N/A

Producing Formation Miss. Depth to Top 2303 Bottom 2336 T.D. 2336

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
	water	0	210	8 5/8	210	none
	water	0	2303	5 1/2	2303	501 ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set
Sand back to 2250 ft, spot 5 sacks cement, pulled pipe at 501 ft.,
bail to 265 ft., slurry mix to surface

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor VAL Energy, Inc. License No. 5822

Address Box 322 Haysville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gear Petroleum Co. Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss. STATE CORPORATION COMMISSION

K. Todd Allam (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.


(Signature) K Todd Allam

(Address) Haysville, Ks. 67060

SUBSCRIBED AND SWORN TO before me this 24th day of September, 19 91

Gary D. Stearns
Notary Public

My Commission Expires:



JUN 27 1991

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

Company	Slusser Drilling Company	Commenced 8/30/69
Contractor	Slusser Drilling Company	Completed 9/2/69
Farm	Haefner #4	NE NE SE 23-17-4E
8 5/8	@ 210	Marion County, Kansas
5 1/2	@ 2303	

Surface soil	5
Shale and lime	50
Shale	100
Shale and shells	210
Lime and shale	475
Shale and lime	600
Shale and shells	845
Shells and shale	1200
Shale and lime	1775
Lime	2035
Lime and shale	2180
Shale and lime	2299
Chat	2303 Rotary T.D.

SLUSSER DRILLING COMPANY #4 HAFENER 23-17-4E
 BOX 275, MARTON, KS. NE NE SE
 Contr. CO. TOOLS Cty. MARION
 Geol. Pool LOST SPRINGS
 E. NONE Cm. 8/29/69 Cp. 9/18/69 IP PMP 15 BOPD + W/
 MISS 2304-36
 API 15-115-20,105

SMP Tops	Depth	Datum
MISS	2299	
TD	2304	
DDTD	2336	

Csg. 8-5/8" 210/130 SX
 5 1/2" 2304/30 SX
 DD 2336 TD, FRAC 30,000# SD +
 10,000 GALS W, SWB LD
 NO DSTS
 NO LOG