

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 33 Twp. 32S Rge. 15W (E) (W)  
Location as "NE/CNWxSWx" or footage from lines C-SE $\frac{1}{2}$ -NE $\frac{1}{4}$   
Lease Owner Sunray DX Oil Company  
Lease Name Vaughn DeGee "A" Well No. 1  
Office Address 300 Union National Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 10-13 19 65  
Application for plugging filed 10-13 19 65  
Application for plugging approved 10-13 19 65  
Plugging commenced 10-13 19 65  
Plugging completed 10-13 19 65  
Reason for abandonment of well or producing formation Dry Hole

NORTH

Section Plat grid with 'X' in the top-right cell.

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elyng  
Producing formation Depth to top Bottom Total Depth of Well 5266 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: Arbuckle, Dry, 5234, 5266, 13 3/8, 227 1/2, 0.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud from 5266' to 200'  
50 sacks cmt. plug 107' to 200'  
Mud from 107' to 40'  
300 sacks cmt. plug from 5' to 40'  
Fill hole with cmt. from 5' to surface

RECEIVED  
STATE CORPORATION COMMISSION

OCT 26 1965  
10-26-65

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address Route 2 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
V.A. Tracy (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V.A. Tracy

300 Union National Bldg. Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 25 day of October, 1965

MAE RESCO

Notary Public.

My commission expires My Commission Expires March 28, 1969

MAE RESCO

COMPANY Sunray DX Oil Company

SEC. 33 T. 32S R. 15W

FARM DeGeer "A" NO. 1

LOC. C SE NE


TOTAL DEPTH 5270'

COUNTY Barber

COMM. 9-30-65

COMP. 10-12-65

CONTRACTOR Garvey Drilling Company



CASING 13 3/8" @ 227' w/300 sx

ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 2628' Shale and Lime
- 2822' Lime and Shale
- 3087' Shale and Lime
- 3160' Shale
- 3460' Shale and Lime
- 4180' Lime and Shale
- 4548' Lime
- 4590' Lime and Chert
- 5156' Lime
- 5199' Sand and Lime
- 5270' Lime
- 5270' RTD

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 26 1965  
10-26-65  
CONSERVATION DIVISION  
Wichita, Kansas

State of Kansas }  
County of Barton } 89

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the DeGeer "A" #1 well.

*Sam N. Stephens*

Subscribed and sworn to before me this 22nd day of October 19 65

My Commission Expires: May 28, 1969

*Richard W. Dangler*  
NOTARY PUBLIC