

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Harper County, Sec. 1 Twp. 32S Rge. 9 E/W  
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines  
NW NW NW


Lease Owner Graves Drilling Co., Inc.  
Lease Name Dusenbury Well No. 1  
Office Address 910 Union Center, Wichita, KS.  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry hole

Date Well completed 23 October 1979  
Application for plugging filed 23 October 1979  
Application for plugging approved 23 October 1979  
Plugging commenced 23 October 1979  
Plugging completed 23 October 1979  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 4450  
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	204'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud to 210'. Pumped 40sacks cement thru drill pipe with pump truck. Pushed plug and 1/2 sack hulls to 40' and pumped 12 sacks cement thru drill pipe with pump truck to base of well cellar. Plugged rat hole with 3 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling CO., Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Court Graves (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Court Graves  
910 Union Center, Wichita, Ks 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 31st. day of October, 19 79

My commission expires 17 May 1983 REBECCA L. MATTHEWS Notary Public.

NOV 01 1979  
11-1-79  
CONSERVATION DIVISION  
Wichita, Kansas

15-077 20553-0000

ROTARY DRILLERS' LOG

OPERATOR: Graves Drilling Co., Inc.  
910 Union Center  
Wichita, Kansas 67202

OPERATIONS COMMENCED: 15 October 1979

CONTRACTOR: Graves Drilling Co., Inc.  
910 Union Center  
Wichita, Kansas 67202

OPERATIONS COMPLETED: 23 October 1979

CASING RECORD: 5 Jts. 204' of used 8-5/8"  
cemented with 180 sacks

LOCATION: Dusenbury No. 1  
NW-NW NW  
Section 1-32S-9W  
Harper Co., Kansas

0 - 204	Red bed
204 - 1787	Red bed and shale
1787 - 4221	Shale and lime
4221 - 4334	Lime & shale
4334 - 4405	Shale and lime
4405 - 4415	Lime
4415 - 4450	Shale and lime
4450	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By Court Graves  
Vice-President

STATE OF KANSAS )  
SEDGWICK COUNTY )

SS:

Subscribed and sworn to before me, a Notary Public, this 30th day of October, 1979

My commission expires: 17 May 1983

Rebecca L. Matthews  
Rebecca L. Matthews Notary Public

