


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 35 Twp. 32S Rge. 11 (E) W(W)  
Location as "NE/CNW/SW" or footage from lines SE SW  
Lease Owner Dozer - Spencer  
Lease Name Wheat Well No. 1  
Office Address 310 South Purdy Lyons, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed May 17 19 62  
Application for plugging filed May 17 19 62  
Application for plugging approved May 17 19 62  
Plugging commenced May 17 19 62  
Plugging completed May 17 19 62  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well \_\_\_\_\_  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4570 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	244'	8-5/8"	244	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

4570' to 235' - Heavy rotary mud  
235' to 173' - Plug, 1/2 sack hulls, 20 sacks cement  
173' to 40' - Heavy rotary mud  
40' to 4' - Plug, 1/2 sack hulls, 10 sacks cement  
4' to 0 - Cellar  
rathole - 25 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 29 1962  
5-29-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Peel Brothers, Inc.  
Address P. O. Box 359 Hoisington, Kansas

STATE OF KANSAS, COUNTY OF BARBER, ss.  
Peel Brothers, Inc. (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. PEEL BROTHERS, INC.

(Signature) BY: *Mendell G. Peel*  
P. O. Box 359 Hoisington, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of May, 19 62  
*Ruch Brant*  
Notary Public.

My commission expires April 27, 1964



15-087-01701-0000  
DRILLERS' LOG

Well Owner: Doser - Spencer  
Well Name: Wheat Well No. 1  
Total Depth: 4570'  
Commenced: 5/3/62  
Completed: 5/17/62  
Casing: 8-5/8" @ 244' cas.  
Contractor: Peel Brothers, Inc.

SE SW  
Sec. 35, Twp. 32S, Rge. 11W  
County: Barber,  
Kansas  
Elevation:  
Productions: Dry

Figures below indicate bottoms of formations:

Red bed	0 -	241
Red bed & shells		1080
Shale & shells		1675
Shale		1789
Lime & shale		1950
Lime		2055
Lime & shale		2780
Shale & shells		2955
Lime & shale		3694
Lime		4381
Lime & shale		4420
Lime		4480
Lime & shale		4502
Lime & chert		4532
Lime & shale		4565
Lime		4570
Total Depth		4570

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 20 1962  
8-20-62  
CONSERVATION DIVISION  
Wichita, Kansas

This is to certify that the above information is to the best of our knowledge, true and correct.

PEEL BROTHERS, INC.

Wendell G. Peel  
BY

SUBSCRIBED AND SWORN to before me this 21 day of May, 1962.

My commission expires: April 27, 1964. Ruth Brant  
Notary Public