

15-007-21066-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

C NW NE
COUNTY Barber SEC. 29 TWP. 32 RGE. 11 W
Location as in quarters or footage from lines: EW

Locate Well
correctly on above
Section Platt.

Lease Owner Eagle Explorations, Inc.
Lease Name Lukens Well No. 1
Office Address Star Route Pratt, Kansas 67124
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed 12-5-81
Application for plugging filed 1983
Plugging commenced Oct. 31, 1983
Plugging completed Nov. 1, 1983
Reason for abandonment of well or producing formation

Not economical to produce

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation Mississippi Depth to top 4703 bottom 4719 T.D. 4955'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
		0	414	8 5/8	414	0
		0	4955	5 1/2	4955	3780'


Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set. Sand from 4729 to 4584, dumped 5 sx. cement on
top of sand, pulled 3780' 5 1/2 casing. Pumped 3 sx. hulls, 20 sx. gel, 1 hull.
Released 8 5/8 plug, pumped 125 sx. 60-40 poz mix, 2% gel, 3% calcium chloride.
Max. pumped 500#, SI 400#. Job completed at 10:00 AM, 11-1-83.

RECEIVED
STATE CORPORATION COMMISSION

MAR 12 1984
3-12-84
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pratt Well Service, Inc.

STATE OF Kansas COUNTY OF Pratt, ss.
Judy Berry (employee of owner) or (~~XXXXXXXXXXXXXXXX~~) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.



(Signature) Judy Berry
Box 847 Pratt, Ks. 67124
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of November 1983

Charlene M. Dudley
Notary Public

My Commission expires: 9/10/86

RECEIVED
STATE CORPORATION COMMISSION
NOV 28 1983
11-28-83
CONSERVATION DIVISION
Wichita, Kansas