

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERRY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

15-007-21066-0000

API NUMBER 15-007-066

LEASE NAME Lukens #1

WELL NUMBER #1

SPOT LOCATION C-NW-NE

SEC. 29 TWP. 32 RGE. 11 (E) OR (W)

COUNTY Barber

DATE WELL COMPLETED 15-12-81

PLUGGING COMMENCED 10-31-83

PLUGGING COMPLETED 11-1-83

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Eagle Exploration, Inc.

ADDRESS Star Route, Pratt, KS 67124

PHONE # (316) 672-7694 OPERATORS LICENSE NO. 5073

CHARACTER OF WELL Oil  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City

IS ACC-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? \_\_\_\_\_

PRODUCING FORMATION Mississippi DEPTH TO TOP 4,703' BOTTOM 4,719' T.D. 4,955'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	414	8 5/8	414	0
		0	4955	5 1/2"	4,955	3780

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. Sand from 4,729' - 4,584', dumped 5 sax cement on top of Sand, pulled 3,780' 5 1/2" casing. Pumped 3 sax HULLS, 20 sax gel, 1-HULL. Released 8 5/8" plug, pumped 125 sax 60-40 poz; 2% gel; 3% Calcium Chloride. Max. pumped 500#, SI 400#  
Job completed @ 10:00 am. 11-1-83

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Pratt Well Service LICENSE No. 5893  
ADDRESS Hwy. 61, Pratt, KS. 67124

STATE OF Kansas - COUNTY OF Pratt, SS.

(EMPLOYEE OF OPERATOR) OR  
(OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Jack A Ford  
(ADDRESS) Star Route, Pratt, KS 6712

SUBSCRIBED AND SWORN TO BEFORE ME THIS 2 DAY OF November, 1983

Deana Pelz  
NOTARY PUBLIC

MY COMMISSION EXPIRES: 3-25-84



RECEIVED  
STATE CORPORATION COMMISSION

FORM CP-4  
REVISED 06-83

NOV 14 1983  
11-14-83  
CONSERVATION DIVISION  
Wichita Kansas