

15-077-00217-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper County. Sec. 8 Twp. 32 Rge. (E) 9 (W)
Location as "NE/CNW/SW" or footage from lines SW NW NW
Lease Owner Pickrell Drilling Company
Lease Name Kloefkorn Well No. 1
Office Address 705 Fourth Nat'l Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 9/28/56 19
Application for plugging filed 9/28 19 56
Application for plugging approved 9/28 19 56
Plugging commenced 9/28 19 56
Plugging completed 9/28 19 56
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation 4344 Depth to top Bottom Total Depth of Well 4448 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	160'	8 5/8"	160'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy mud to 160', bridge hole and
cement with 20 sacks. Then heavy mud to 20'
below cellar, bridge hole & cement with 10 sacks
to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth Nat'l Bank Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) PICKRELL DRILLING COMPANY
C. W. Sebitts

SUBSCRIBED AND SWORN TO before me this 30th day of October, 19 56

My commission expires July 30, 1958

Sebastian H. Peter Notary Public.

PLUGGING
FILE SEC. 8 T. 32 R. 9W
BOOK PAGE 103 LINE 22

RECEIVED
OCT 4 1956
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

15-077-00217-0000
ROTARY DRILLING LOG

COMPANY: **Pickrell Drilling Company, etal**
Wichita, Kansas

Rotary Drilling Commenced 9/14/56

Rotary Drilling Completed 9/29/56

LOCATION: **SW NW NW Sec. 8-32-9W, Harper County, Kansas**

Kloefkorn

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: **160' (4 jts.) 8 5/8" 22.7# Armcoc Spiralweld Casing set at 160' with 125 sacks cement circulated.**

Filled with heavy mud to 160', bridge hole and cement with 20 sacks. Then heavy mud to 20' below cellar, bridge hole & cement with 10 sacks to bottom of cellar.

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing.)

Sand	85	Circ. for samples at	3463
Red Rock	160		3524
Shale	955		4349
Salt, Shale & Shells	1390		4360
Lime	2195		4376
Lime & Shale	2320		4385
Shale	2550		4395
Lime	2810		4400
Lime & Shale	3050		4448
Lime	3236		
Sandy Shale & Lime	3342		
Lime & Shale	3427		
Lime & Sand	3605		
Lime	3672		
Lime & Shale	3757		
Lime	4221		
Lime & Shale	4267		
Lime	4344		
Mississippi	4385		
Mississippi Lime	4400		
Mississippi	4443		
Lime	4448 T.D.		

S.L.M. at 1500 - O.K.
 3000 - "
 4000 - "

Slope Test at 1500 - 0° off
 3000 - 0° off
 4000 - 0° off

PLUGGING

FILE SEC. 8 T. 32 R. 9W
 BOOK PAGE 103 LINE 22

STATE OF KANSAS
 10-5-56
 CONSERVATION DIVISION
 WICHITA, KANSAS

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By C. W. Sebitts
 Attorney-in-Fact

STATE OF KANSAS, }
 COUNTY OF SEDGWICK } ss.:

On this 4 day of October, 1956, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: July 30, 1958

Shirley D. Heter
 Notary Public