

LEASE NAME McClure

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 30 TWP. 32S RGE. 11 ~~W~~ (W)

COUNTY Barber

Date Well Completed

Plugging Commenced 8-15-96

Plugging Completed 8-19-96

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Casey Musgrove Oil

ADDRESS Rt. 2, Box 401, Ponca City, OK 74604

PHONE# (405) 765-6590 OPERATORS LICENSE NO. 3308

Character of Well good

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-15-96 (date)

by Steve Piefer (KCC District Agent's Name)

Is ACO-1 filled? yes If not, is well log attached? no

Producing Formation Depth to Top 3555 Bottom 3567 T.D. 3744

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	209	None
				4 1/2	3744	2500

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each section. Lay down rods and tubing, sand well back to 3370, dump 4sx portland with dump bailer, stretch and cut pipe at 2500, lay down 4 1/2 casing. Allied pump 300 hulls, 10 jel, 50sx cement, 10 jel 100 hulls, 100sx cement, 60/40 6%.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Casey Musgrove KANSAS CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Barber

RECEIVED
KANSAS CORPORATION COMMISSION
8-27-96
AUG 27 1996

Alan Vratil (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed with the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Medicine Lodge, KS 67104



SUBSCRIBED AND SWORN TO before me this 21 day of August, 19 96

Glenda Morrison
Notary Public

My Commission Expires: 10/14/98