

1050308

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,882 -0000

SE NE , SEC. 8 , T 32 S, R 15 W/X  
3300 feet from ~~XXX~~ section line  
660 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9682

Lease Name Marsh Well # 1-8

Operator: Harry A. Spring

County Barber

Name & Address P. O. Box 2225

Well Total Depth 5392 <sup>175.24</sup> feet

Ardmore, OK 73402

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 426

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hughes Drilling Co., Inc. License Number 6431

Address P. O. Box 6001, Enid, OK 73702

Company to plug at: Hour: 10:00 am Day: 9 Month: August Year: 19 84

Plugging proposal received from Tom Spring

(company name) Harry A. Spring (phone) 405-226-1910

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1020' with 50 sx cement

2nd plug at 450' with 40 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacy  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:00 pm Day: 9 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1020' with 50 sx cement, 2nd plug at 450' with 40  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to

circulate mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 16 1984  
8-16-84  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun

(If additional description is necessary, use BACK of this form)

observe this plugging.

INVOICED

DATE 8-17-84

INV. NO. 3232

8-9

Signed Richard W. Lacy  
(TECHNICIAN)

50