

To: 1 040743 3-10
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6707
Operator: Red Canyon Oil
Name:
Address 1241 Sullivan Circle
Wichita, KS 67204

API NUMBER 15-N/A 15-007-1001-00-01
NW SW SE, SEC. 7, T 32 S, R 15 W/EX
990 feet from S section line
2310 feet from E section line
Lease Name Rusk A Well # 1
County Barber
Well Total Depth 4870 158.27 feet
Conductor Pipe: Size feet
Surface Casing: Size 10 3/4 feet 200

Abandoned Oil Well X Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 9:30 a.m. Day: 10 Month: 3 Year: 19 93
Plugging proposal received from Jeff Sletto
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4750', PBTD 4200', Perfs at 4164-67, 4651-55'
1st plug sand back to 4114' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 125 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part None
Operations Completed: Hour: 10:30 a.m. Day: 10 Month: 3 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 4114' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 125 sx cement.

Maximum pressure 300 psi and shut in 200 psi.

RECEIVED
STATE CORPORATION COMMISSION
3-17-93
MAR 17 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1600' of 4 1/2" casing. CONSERVATION DIVISION
Additional description is necessary, use BACK of this form. WICHITA, KANSAS

DATE (did /) observe this plugging.

3-18-93
37488

Signed Stephen J. P...
(TECHNICIAN)