

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21337-00-00  
Spot: SWSWSE Sec/Twnshp/Rge: 12-10S-18W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: ANDRESON A Well #: 1  
County: ROOKS Total Vertical Depth: 3754 feet

Operator License No.: 32278  
Op Name: TENGASCO, INC.  
Address: 1327 NOOSE RD PO BOX 458  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3751		175 SX
SURF	8.625	231		160 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/09/2013 8:00 AM  
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.  
Proposal Rcvd. from: GARY WAGNER Company: FISCHER WELL SERVICE, INC. Phone: (785) 625-6374

Proposed Alt II 1490' w/500 sx cwc.  
Plugging LKC perforations: 3544' - 3638'  
Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/09/2013 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3590'. Allied pumped 120 sx cement w/200 # hulls. Pulled tubing to 1800'. Allied pumped 125 sx cement w/250 # hulls. Cement circulated. PTOH. Topped off 4 1/2" casing w/5 sx cement. Casing full. Hooked up to backside and pumped 15 sx cement. Maximum pressure 300 psi. Shut in pressure 300 psi.

Perfs:

Top	Bot	Thru	Comments
3544	3638		

**KCC WICHITA**

Remarks: ALLIED  
Plugged through: TBG

**SEP 17 2013**  
**RECEIVED**

District: 04

Signed Richard Williams  
09/09/13 (TECHNICIAN)

CM

**SEP 12 2013**