

8-9-87

To: 1 030837  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-22,159-00-00  
SE NW SE, SEC. 1, T 32 S, R 13 W/E  
1650 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5171  
Operator: TXO Production Corporation  
Name & Address: 155 North Market, Suite 1000  
Wichita, KS 67202

Lease Name Fitzsimmons Well # 1  
County Barber 143.49  
Well Total Depth 4415 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drilling, Inc. License Number 5107  
Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 6 a.m. Day: 9 Month: 8 Year: 19 87

Plugging proposal received from Robby  
(company name) TXO Production Corporation (phone) 316-269-7662

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 1579'  
Anhydrite 1850'

- 1st plug at base Anhydrite with 50 sx cement,
- 2nd plug at 300' with 50 sx cement,
- 3rd plug at 40-0' with 10 sx cement,
- 4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 7:30 a.m. Day: 9 Month: 8 Year: 19 87

- ACTUAL PLUGGING REPORT
- 1st plug at 1850' with 50 sx cement,
  - 2nd plug at 300' with 50 sx cement,
  - 3rd plug at 40-0' with 10 sx cement,
  - 4th plug to circulate rathole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 11 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(Do not) observe this plugging.

DATE 8-12-87

Signed Steve Permut  
(TECHNICIAN)

INV. NO. 17790  
8-9

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date July 29, 1987

API Number 15-007-22,159-0000

OPERATOR: License # 5171
Name TXO Production Corp
Address 155 N. Market, Ste 1000
City/State/Zip Wichita, KS, 67202
Contact Person Jeffrey S. Childs
Phone (316) 269-7662

SE NW SE Sec. 1 Twp. 32S S, Rg. 13 XX West
1650' Ft. from South Line of Section
1650' Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5107
Name H-30 Drilling, Inc.
City/State Wichita, Kansas 67202

Nearest lease or unit boundary line 1650' feet
County Barber
Lease Name FITZSIMMONS Well # 1
Ground surface elevation TBD feet MSI

Well Drilled For: Well Class: Type Equipment:
Oil Storage Infield X Mud Rotary
X Gas Inj X Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water:
Depth to bottom of usable water 200'

If OWWO: old well info as follows:

Surface pipe planned to be set 250'
Conductor pipe required none
RIGEL/Total Depth 4350' feet

Operator
Well Name
Comp Date Old Total Depth

STATE CORPORATION COMMISSION Mississippi Chert

I certify that well will comply with K.S.A. 55-101, et seq. plus eventually plugging hole to KCC specifications.
Date 7/28/87 Signature of Operator or Agent [Signature] Rule Drlg & Prod Engineer

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Elevation 200 feet per Alt. 00
This Authorization Expires 1-28-88 Approved Date 7-28-87

Get 250' at 6:18 on 8-1-87 AL

SE NW SE Sec. 1 Twp. 32S S, Rg. 13 XX West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays)

1st plug @ ft. deep 50 8XB or formation with 1100 feet of 60/40 Poz w/ 6% gal
2nd plug @ ft. deep 50 8XB or formation with 300 feet of
3rd plug @ ft. deep 10 8XB or formation with 40-0 feet of
4th plug @ ft. deep or formation with feet of
5th plug @ ft. deep or formation with feet of
(2) Rathole to surface minus 5 feet 10 8XB (b) Mousehole to surface minus 5 feet 10 8XB

PUSHER Robby -
TD 4415 FORMATION MISS
SURFACE PIPE 8 7/8 @ 252
ANHYDRITE 1850 ELEVATION 1579
STARTING TIME & DATE 6:00 AM 8-7
COMPLETION TIME & DATE 7:30 AM 8-9-87
1st PLUG @ 1850 FT. W/ 50 SX
2nd PLUG @ 300 FT. W/ 50 SX
3rd PLUG @ 40-0 FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 10 SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ Abund.
CEMENT COMPANY B.J. T. Inc
TECHNICIAN G/4 60%

RECEIVED
STATE CORPORATION COMMISSION
AUG 11 1987
CONSERVATION DIVISION
Wichita, Kansas