

3-6

To: 1 040232
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,565 -00-00
App. SE SE SE, SEC. 8, T 32 S, R 13 W/E
480 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: TXO Production Corporation
Name & Address 1660 Lincoln, Suite 1800
Denver, CO 80264

Lease Name Gant Well # C-1
County Barber
Well Total Depth 4450 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 389

Abandoned Oil Well Gas Well _____
Other well as hereinafter indicated _____

RECEIVED
STATE CORPORATION COMMISSION
MAR 13 1989
CONSERVATION DIVISION
Wichita, Kansas

Plugging Contractor Clarke Corporation License Number 5105
Address Box 187, Medicine Lodge, KS 67104
Company to plug at: Hour: 9:30 a.m. Day: 6 Month: 3 Year: 19 89

Plugging proposal received from Elmo Morgenstern
(company name) Clarke Corporation (phone) 316-886-5606

were: 4 1/2" at 4490' PBTB 4490' CIBP at 4100' Perfs at 3940-44, 3972-76'
1st plug sand back to 3890' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:15 a.m. Day: 6 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3900' and dumped 4 sx cement on top of
sand through bailer,
2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 2% gel, 2% cc by B.J. Titan. Recovered 2800' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 3-14-89
INV. NO. 24096

Signed Stephen J. P. Puffer
(TECHNICIAN)