

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21925-00-00
Spot: E2SESESW Sec/Twnshp/Rge: 18-7S-17W
330 feet from S Section Line, 2485 feet from W Section Line
Lease Name: HOUSING AUTHORITY Well #: 1
County: ROOKS Total Vertical Depth: 3824 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 1327 NOOSE RD PO BOX 458
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3288		
COND	17.25	86		80 sx
PROD	5.5	3323		125 SX
SURF	8.625	1219		425 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/11/2013 8:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.
Proposal Rcvd. from: GARY WAGNER Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Alt I 1219' w/425 sx cement
Plugging 8 5/8" x 5 1/2" annulus cemented w/225 sx on 06-87
Method: Topeka perforations: 2940' - 2944'
LKC perforations: 2999' - 3196'
ARB perforations: 3268' - 3282'
Ordered 400 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/11/2013 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3263'. Allied pumped 150 sx cement w/400 # hulls.
Pulled tubing to 1630'. Allied pumped 175 sx cement w/200 # hulls. Cement circulated.
PTOH. Topped 5 1/2" casing off w/20 sx cement.
Hooked up to backside with instant pressure.

Perfs:

Top	Bot	Thru	Comments
3268	3282		
2999	3196		
2940	2944		

Remarks: ALLIED
Plugged through: TBG

KCC WICHITA

SEP 17 2013
RECEIVED

District: 04

Signed Richard Williams
09/07/13 (TECHNICIAN)

CM

SEP 12 2013