

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24610-00-00  
Spot: NESENW Sec/Twnshp/Rge: 27-12S-17W  
3630 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: THERESA Well #: 2  
County: ELLIS Total Vertical Depth: 3740 feet

Operator License No.: 5252  
Op Name: R. P. NIXON OPERATIONS, INC  
Address: 207 W 12TH  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3702		
PROD	5.5	3733		100 SX
SURF	8.625	235		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/26/2013 9:30 AM  
Plug Co. License No.: 5252 Plug Co. Name: R. P. NIXON OPERATIONS, INC  
Proposal Rcvd. from: DUANE ACHTERBERT Company: R. P. NIXON OPERATIONS, INC. Phone: (785) 656-0038

Proposed Plugging Method: Ordered 310 sx 60/40 pozmix 4% gel cement; 500 # hulls; 13 sx gel  
PBTB-3702'  
Perforations- ARB-3648' - 3650'; 3642' - 3644'; 3631' - 3633'  
GPS: 38.98275 -099.19724  
3589' FSL 3019' FEL  
SW NE SE NW

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/26/2013 12:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 1850' - 1304' - 750'.  
Stewart Well Service ran in hole with tubing to 3527'. Allied rigged to tubing and mixed and pumped 13 sx gel followed by 50 sx cement with 200 # hulls mixed in.  
Pulled tubing to 1862'. Allied rigged to tubing and mixed and pumped 100 sx cement w/200 # hulls.  
Pulled tubing to 862'. Allied rigged to tubing and mixed and pumped 85 sx cement with 100 # hulls to circulate cement to surface.  
Pulled tubing. Topped off 5 1/2" casing with 15 sx cement. Hole standing full.  
Rigged to 8 5/8" casing and pumped 15 sx cement to pressure with 200 psi and 200 psi shut in pressure.

Perfs:

Top	Bot	Thru	Comments
3648	3650		
3642	3644		
3631	3633		

RECEIVED  
KANSAS CORPORATION COMMISSION

SEP 09 2013


CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING CO. TICKET # 56997

Plugged through: TBG

District: 04

Signed

  
10/01/13 (TECHNICIAN)

CM

AUG 29 2013