

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23880-00-00
Spot: SWNENESW Sec/Twnshp/Rge: 36-24S-4E
2040 feet from S Section Line, 2070 feet from W Section Line
Lease Name: BUTLER LAURA Well #: 1
County: BUTLER Total Vertical Depth: 2667 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2666		160 SX
SURF	8.625	212		125 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 05/21/2013 5:00 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE Phone: (620) 960-1288

Proposed Plugging Method: AS PER KCC RULES & REGS/CIBP @ 2610 W/2 SKS 265'-0'. 60/40 POZ 4% GEL.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: NONE
Date/Time Plugging Completed: 05/23/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2610, DUMP BAILED 2 SXS CEMENT ON TOP. RIH ON WIRELINE SHOT SQUEEZE HOLES 265'-266'. RIH W/ TUBING @ 265, GRESSEL OILFIELD MIXED & PUMPED 130 SXS 60/44 POZMIX TO SURFACE. P&A COMPLETE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2664	2667	OH	
1427	2667		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 13 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: GRESSEL CEMENT TICKET #42008

Plugged through: TBG

District: 02

Signed

Duane Krueger
8/13/13
(TECHNICIAN)

JK