

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23843-00-00
Spot: S2NWSWNW Sec/Twnshp/Rge: 26-24S-4E
1695 feet from N Section Line, 330 feet from W Section Line
Lease Name: PHILLIPS Well #: 4
County: BUTLER Total Vertical Depth: 2652 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2652		150 SX
SURF	8.625	222		230 SX
T1	2.375	2636		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/21/2013 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE Phone: (620) 960-1288

Proposed Plugging Method: AS PER KCC RULES & REGS, CIBP @ 2475 W 2 SXS 275-0'

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 05/23/2013 9:15 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2475, DUMP BAILED 2 SX CEMENT ON TOP. RIH ON WIRELINE SHOT SQUEEZE HOLES 275'-276'. RIH W/TUBING @ 275', GRESSEL OILFIELD MIXED & PUMPED 135 SXS 60/44 POZMIX TO SURFACE CEMENT CIRCULATED. P&A COMPLETE

Perfs:

Top	Bot	Thru	Comments
2588	2602	CSG	
2576	2583	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: GRESSEL CEMENT TICKET #42007

Plugged through: TBG

AUG 13 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Duane Krueger
8/12/13
(TECHNICIAN)