

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-23394-00-00  
Spot: NWSENEW Sec/Twnshp/Rge: 31-26S-7E  
680 feet from N Section Line, 2250 feet from W Section Line  
Lease Name: WAIT Well #: 1  
County: BUTLER Total Vertical Depth: 2755 feet

Operator License No.: 5120  
Op Name: RANGE OIL COMPANY, INC.  
Address: 9412 E. CENTRAL PO BOX 781775  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2752		190 SX
SURF	8.625	264		165 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/20/2013 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE Phone: (620) 960-1288

Proposed Plugging Method: AS PER KCC RULES & REGS/ CIBP @ 2650 W/2 SKS 315-0'. 60/40 POZMIX 4% GEL.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE  
Date/Time Plugging Completed: 05/23/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE, SET CIBP @ 2650, DUMP BAILED 2 SXS CEMENT ON TOP. RIH ON WIRELINE SHOT SQUEEZE, HOLES 315'-316'. RIH WIRELINE SHOT SQUEEZE HOLES 315'-316'. RIH W/TUBING @ 315' GRESSEL OILFEILD MIXED & PUMPED 285 SXS 60/40 POZMIX 4% GEL TO SURFACE. P&A COMPLETE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2711	2714		CSG

RECEIVED  
KANSAS CORPORATION COMMISSION

Remarks: GRESSEL OILFIELD CEMENT TICKET #40011.

**AUG 13 2013**

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed

Duane Krueger  
9/12/13  
(TECHNICIAN)

1/2K