

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-23429-00-01
Spot: SENWNWNE Sec/Twnshp/Rge: 31-26S-7E
4655 feet from S Section Line, 2127 feet from E Section Line
Lease Name: WAIT Well #: 3
County: BUTLER Total Vertical Depth: 2773 feet

Operator License No.: 5120
Op Name: RANGE OIL COMPANY, INC.
Address: 9412 E. CENTRAL PO BOX 781775
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2767		75 SX
SURF	8.625	265		180 SX

Well Type: EOR UIC Docket No: E27126.1 Date/Time to Plug: 05/21/2013 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: GEORGE RAYL Company: GRESSEL OILFIELD SERVICE Phone: (620) 960-1288

Proposed Plugging Method: AS PER KCC RULES & REGS, CIBP @ 2675 W/2 SKS 315'-0'. 60/40 POZMIX 4% GEL.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 05/23/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2675, DUMP BAILED 2 SXS CEMENT ON TOP. RIH ON WIRELINE SHOT SQUEEZE HOLES @ 315-316'. RIH W/TUBING @ 315'. GRESSEL OILFIELD SERVICE MIXED & PUMPED 155 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN.

Perfs:

Top	Bot	Thru	Comments
1435	2773		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: GRESSEL OILFIELD CEMENT TICKET #40010

Plugged through: TBG

AUG 13 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

DUANE KRUEGER
9/13/13 (TECHNICIAN)

cc to VMC 8/13/13