

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04342-00-00
Spot: SESENW Sec/Twnshp/Rge: 4-18S-14W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: FRIEB C Well #: 1
County: BARTON Total Vertical Depth: 3450 feet

Operator License No.: 4323
Op Name: REICHLINGER, GARY DBA REICHLING
Address: 118 W 8TH ST PO BOX 4
YORK, NE 68467

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3380		
COND	13.375	257		200 SX
PROD	6	3437		300 SX
SURF	8.625	935		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/18/2013 9:30 AM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: GARY REICHLINGER Company: REICHLINGER BUS. Phone: (402) 362-4191

Proposed
Plugging
Method:

Ordered 450 sx 60/40 pozmix 4% gel cement w/400 # hulls and 13 sx gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/18/2013 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforations at 1500', 950' and 240'.
Ran tubing to 3300' and pumped 13 sx gel followed by 60 sx cement w/100 # hulls. Had cement early on first plug.
Pulled tubing. Found hole in tubing.
Pulled tubing to 1550' and pumped 220 sx cement w/300 # hulls. Circulated cement to surface.
Had cement on casing and surface pipe.

GPS: 38.51498 -098.87746

Perfs:

Top	Bot	Thru	Comments
3349	3352		
3211	3215		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 02 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING OF RUSSEL

Plugged through: ESGT3G

District: 04

Signed Bruce Rodie
9/12/13 (TECHNICIAN)

CM

JUL 30 2013