


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Ness County, Sec. 33 Twp 18 Rge. (E) 21 (W)

Location as "NE/CNW4SW4" or footage from lines _____
Lease Owner Colorado Oil & Gas Co. Corp.
Lease Name Miner Well No. 1
Office Address 1020 Hoover, Great Bend, Kansas - 67530
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced September 8, 1965
Plugging completed September 14, 1965
Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	309'	NONE
				5 1/2"	NONE	2032'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Raise Mast, Checked hole and cleaned cellar
Sanded Hole to 4190' and dumped 4 sacks of cement with dump bailer.
Rigged up on 5 1/2" casing. Shot pipe @ 3547', Pressured up, shot pipe @ 3652', pressured up, shot pipe @ 3360', pressured up. Shot pipe @ 3264', pressured up. Left. pressure on pipe.
Pumped 80 barrels of oil and pumped plug to 3200'.
Worked pipe, no change in tension.
Shot pipe @ 2773', 2588', 2400', 2213' & 2027'. Worked pipe loose and pulled 38 joints of 5 1/2" casing.
Pumped in 60 sacks of weight mud and 28 sacks of gel mud. Pulled pipe to 450' and pumped in 30 sacks of cement. Pulled pipe to 160' and pumped in 30 sacks of cement. Pulled pipe and Capped well with 5 sacks of cement.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1965

My commission expires May 27, 1969
Alice Ochs Notary Public.

ROTARY DRILLING LOG

15:135-00367-0000

OPERATOR: Colorado Oil and Gas Corporation
#1 MINER, C NW NW
Section 33-138-21W
Ness County, Kansas

CONTRACTOR: Rains &
Williamson Oil Co.
COMMENCED: 8-8-63
COMPLETED: 8-22-63

Remarks: Set 8-5/8" sur-
face casing at
304' with 200
sacks cement

Formations

Surface Soil	50'
Sand	100'
Clay and Shale	390'
Blue Shale	450'
Shale w/Sand	590'
Red Bed	836'
Sand	1045'
Shale and Red Bed	1351'
Anhydrite	1385'
Shale and Shells	1523'
Shale and Lime	2135'
Lime and Shale	2565'
Lime	2630'
Lime and Shale	3020'
Shale and Lime Streaks	3070'
Shale and Lime	3286'
Lime	4214'
Rotary Total Depth	4214'

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1963

CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is
true and correct to the best of
our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains
Partner

Subscribed and sworn to before me, a
Notary Public in and for the State of
Kansas, County of Sedgwick, this 26th
day of August, 1963.

Sherry Gish
Sherry Gish Notary Public

My Commission Expires:
November 8, 1966