

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135,21,044-60000

LEASE NAME Ryersee

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER "A" #1

2970 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 36 TWP. 18 RGE. 21 (E) or (W)

COUNTY Ness

LEASE OPERATOR John J. Darrah, Jr.

ADDRESS 412 E. Was Thunderbird Douglas, Suite One, Wichita, Ks. 67202

PHONE # (316-685-4467) OPERATORS LICENSE NO. 5088

Date Well Completed _____

Character of Well oil

Plugging Commenced 5-13-87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-29-87

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? One

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4206'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	305'	None
				5-1/2"	4198'	2,313.51'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 4090' and 5 sacks cement. Shot casing at 2500' and 2300'. Pulled 73 joints of 5-1/2" casing. Allied squeezed well with 3 sacks hulls, 10 sacks gel, 50 sacks cement, 10 sacks gel, 1 sack hulls, released plug and pumped 150 sacks 60/40 pozmix cement with 6% added gel. Maximum pressure was 800 psi and shutin 200 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 10th day of June, 1987

My Commission Expires: _____
IGNA M. LEATHERMAN Notary Public
Barton County, Kansas
My Appt. Exp. 9-26-87



JUN 12 1987

6-12-87

15-135-21044-0000

DRILLERS LOG

Company Thunderbird Drilling, Inc.

Contractor Thunderbird Drilling, Inc.

Elevation 2139 K. B.

Farm Ryersee "A"

Well No. 1

Casing 8 5/8" @ 305' w/200 sx.

Location SW SW NW Sec. 36-18S-21W

Production 5 1/2" @ 4198' w/100 sx.

County Ness


<u>From</u>	<u>To</u>	<u>Description</u>
0	20	Rock
20	305	Surface Hole
305	330	Shale
330	777	Shale & Red Bed
777	995	D. Sand
995	1350	Shale & Shells
1350	1385	Anhydrite
1385	3200	Shale & Shells
3200	4130	Shale & Lime
4130	T. D.	Lime

STATE OF KANSAS)
) ss.
 COUNTY OF SEDGWICK)

I, Burke Krueger, of Thunderbird Drilling, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your #1 Ryersee "A"



Subscribed and sworn to before me this 29th day of May, 1975


 Glenda Hill Notary Public

My commission expires: 3-8-77

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 13 1987
 CONSERVATION DIVISION
 Wichita, Kansas