

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-62-3-117

API NUMBER 15-015-19086-00-00

LEASE NAME DUNKLE

WELL NUMBER 9

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Coas. Div.
 office within 30 days.

330 Ft. from S Section Line

3630 Ft. from E Section Line

LEASE OPERATOR LACHENMAYR OIL CO.

SEC. 5 TWP. 25 SRGE. 5 (E) or (W)

ADDRESS 904 EMMALINE NEWTON, KS 67114

COUNTY BUTLER

PHONE (316) 283-2660 OPERATORS LICENSE NO. 06804

Date Well Completed 10/10/17

Character of Well OIL

Plugging Commenced 10/19/01

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 10/31/01

The plugging proposal was approved on 10/18/01 (date)

by Butch Hoberecht (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? No

Producing Formation Viola Depth to Top 2466' Bottom 2497' T.O. 2497'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Viola	Oil and Water	2466		4 1/2"	2450'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Build bridge @ 2425'. Use dump bailer to spot 5 sks cement. Build @ bridge @ 250'. United Cementing pump 40 sks cement to surface. Rigged down. Used backhoe to open surface casing. United pumped 250 sks cement thru 1" pipe @ 250'

Name of Plugging Contractor K. E. SNYDER CO. License No. 32147

Address HAMILTON, KS

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: HOWARD LACHENMAYR

STATE OF KANSAS COUNTY OF HARVEY, ss.

HOWARD LACHENMAYR (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Howard Lachenmayr
 (Address) 904 EMMALINE NEWTON, KS 67114


SUBSCRIBED AND SWORN TO before me this 18th day of December, 2001

Bernice Capps
 Notary Public

RECEIVED Commission Expires: Aug 4, 2002

DEC 20 2001

KCC WICHITA



OK

United Cementing & Acid Company, Inc.

100 North Broadway, Suite 3300
Oklahoma City, Oklahoma 73102

(405)-606-8500

Plant Location

2510 West 6th Street
El Dorado, Kansas 67042
(316) 321-4680

Customer:

Lachenmayr Oil Co.
901 Emmaline
Newton, KS 67114

Invoice No.
Field Ticket
Date

4069
3442
10/31/01

PO#

Date of Job	County	State	Lease	Well No.
10/31/01	BU	KS	Dunkel	#9
Size of Casing	Depth Of Well	Depth Of Job	Plug Depth	Pressure
		210'		
Quantity	Description	UOM	Unit Price	Total
	OLD HOLE PLUG			
250 sax.	60/40 Pozmix	sax	4.80	1,200.00
10 sax.	Gel	sax	9.50	95.00
3 hrs.	Winch Truck	hr	55.00	165.00
260 sax.	Bulk charge	sax	0.94	244.40
	Drayage (MINIMUM CHARGE)			94.50
10 mi.	Pump Truck Mileage Charge			n/c
	Acid Unit			472.50

Pd
600

Thank you for your continued business

Please Remit To:

100 North Broadway, Suite 3300
Oklahoma City, Oklahoma 73102,

Subtotal	\$2,271.40
Sales Tax	\$ 134.01
Total	\$2,405.41

Terms: Net 30 days From Invoice Date. Please Pay From This Invoice

ORIGINAL INVOICE

RECEIVED

DEC 20 2001

KCC WICHITA

United Cementing & Acid Company, Inc.100 North Broadway, Suite 3300
Oklahoma City, Oklahoma 73102

(405)-606-8500

Plant Location2510 West 6th Street
El Dorado, Kansas 67042
(316) 321-4680

Customer:

Lachenmayr Oil Co.
901 Emmaline
Newton, KS 67114Invoice No.
Field Ticket
Date4037
3438
10/22/01

PO#

Date of Job	County	State	Lease	Well No.	
10/19/01	BU	KS	Dunkle	#9	
Size of Casing	Depth Of Well	Depth Of Job	Plug Depth	Pressure	
2-3/8" inside 4-1/2"					
Quantity	Description	UOM	Unit Price	Total	
	PLUGGING				
40 sax.	60/40 Pozmix	sax	4.80	192.00	
2 sax.	Gel	sax	9.50	19.00	
42 sax.	Bulk Charge	sax	0.94	39.48	
	Drayage (MINIMUM CHARGE)			94.50	
10 mi.	Pump Truck Mileage Charge	mi	2.00	20.00	
	Cement Unit			472.50	
				Subtotal	\$ 837.48
				Sales Tax	\$ 49.41
				Total	\$ 886.89

Please Remit To:

100 North Broadway, Suite 3300
Oklahoma City, Oklahoma 73102**Terms: Net 30 days From Invoice Date. Please Pay From This Invoice****ORIGINAL INVOICE**

RECEIVED

DEC 20 2001

KCC WICHITA