

WELL PLUGGING RECORD

RECEIVED
DEC 04 2001
KCC WICHITA

State Of Kansas
State Corporation Commission
130 S. Market, Room 2078
Wichita, KS 67202

Lease Operator: Petroleum Property Services, Inc.
155 N. Market #1000, Wichita, KS 67202

Phone 316-265-3351

Character of Well: OIL

API Number: 15-015-19080-00-00
Lease Name: JACKSON
Well Number: 1 (12)
2310 Ft. From S Section Line
330 Ft. From E Section Line
Sec: 24 TWP: 25S RGE: 4E
Operators License No. 31142 BUTLER County:
Date Well Completed: 3/44
Plugging Commenced: 11/12/2001
Plugging Completed: 11/13/2001

The plugging proposal was approved on: 11/9/2001

by: BUTCH HOBerecht

KCC District Agent

Is ACO-1 Filed: NO If not, is well log attached? YES

Producing Formation:	Depth to Top	Bottom	T.D.
MISSISSIPPI	2513	2571	2571

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
MISS	O&W	2513	2571	7	2515	0
				4 1/2	2530	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or plugs were used, state the character of same and depth place, from ___ feet to ___ feet each set.

SAND BACK TO 2450', DUMP 5 SX CEMENT 2450-2385'. RUN TUBING BETWEEN 7" & 4 1/2" TO 232', PUMP 350 SX 60/40 POZ FROM 232' TO SURFACE. RUN TUBING INSIDE 4 1/2 TO 250' AND FILL TO SURFACE WITH 99 SX 60/40 POZ. PULL TUBING AND FILL 4 1/2 WITH 10 SX 60/40 POZ. HOLE STAYED FULL.

Plugging Contractor: PETROLEUM PROPERTY SERVICES License No. 31142
Address: 155 NORTH MARKET #1010, WICHITA, KS 67202

Name of Party Responsible For Plugging Fees: Petroleum Property Services, Inc.


STATE OF: KANSAS COUNTY OF: SEDGWICK, SS.
R.J. Thatcher (Employee of Operator) or (Operator), of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Signature: *R.J. Thatcher*
Address: 3535 American Drive, Colorado Springs, CO 80917

SUBSCRIBED AND SWORN TO before me this 3rd day of Dec. 2001

Rosann M. Schipper
Notary-Public

My Commission Expires: 9/28/03



OR

Company: BA E ET AL
 Farm: Jackson "D" No. 1.

SEC. 4
 ME. SE

T. 25 R. 4 E

Total Depth. 2517'

Comm. 1-24-44

Shut or Treated.

Contractor. R.J. Wixson

Issued. 4-15-44

Comp. 3-3-44

RECEIVED

County.

Butler

KANSAS

DEC 04 2001

KCC WICHITA



CASING:
 15 1/2" 230'
 12 1/2" 935'
 10" 1105'

Elevation. _____

Production. 30 B.

Figures Indicate Bottom of Formations.

cellar	8	lime	1025
shale	30	shale	1075
red rock	50	lime (sh gas 1090)	1097
lime	60	shale (HPW 1090-95)	1099
shale	65	lime	1100
gravel & sand	75	shale	1125
lime	95	lime	1130
shale	140	shale	1135
lime	175	lime	1140
shale	190	shale blue	1155
lime	195	shale	1200
shale blue	205	lime	1215
lime	210	shale	1255
shale blue	218	lime	1290
red rock	230	shale	1295
lime	275	lime hd	1305
shale	280	shale	1315
lime	310	lime	1400
shale	315	shale	1405
lime	325	lime 1 1/2" BY	1460
shale	345	shale 6" BY	1480
red rock	347	lime 4" BY	1510
lime	385	shale lime	1540
shale	400	shale	1585
lime	415	lime	1595
shale	425	lime	1606
lime	440	shale	1650
shale	450	lime shells	1660
lime	460	shale sdy	1700
shale	470	shale	1750
lime	515	lime	1775
shale	520	shale	1800
lime (HPW 640)	540	lime (HPW 1860-70)	1890
shale	555	shale	1918
shale & lime	580	lime	2220
lime	600	shale	2225
shale	625	lime	2245
lime	630	shale	2255
shale	655	lime	2270
lime	665	shale	2345
shale	675	lime	2355
lime	690	shale	2375
shale	695	lime	2400
shell & shale	705	shale	2415
shale & lime	730	lime	2445
sand	760	shale	2450
shale	765	lime	2475
lime hd	810	red rock	2477
shale	815	shale	2515
lime shell	830	chat	2517
shale	850	Total Depth.	
sand	695		
lime	915		
wtr sand	920		
lime	965		
shale	970		
lime	980		
shale	990		
lime	995		
shale	1020		

2512 pipe set
 2571 TD

SERVICE TICKET

UNITED CEMENTING & ACID CO., INC.

3452

BOX 712 EL DORADO, KANSAS 67042 PHONE AC 316-321-4680

DATE 11-13-01 COUNTY BUTLER

CHG TO: PPSJ ADDRESS

CITY STATE ZIP

LEASE & WELL NO. JACKSON A-1 SEC. TWP. RNG.

CONTRACTOR PIZZITTS WELL SERVICE TIME ON LOCATION 7:45 A.M.

KIND OF JOB OLD HOLE PLUG

SERVICE CHARGE 250' 472.99

QUANTITY	MATERIAL USED	TYPE	
389 SX	60/40 PDZ-MZY	① 4.80	1867.20
16 SX	9F1	② 9.50	152.00
405 SX	BULK CHARGE	.94	380.79
7	BULK TRK. MILES 20 250' low		99.53
7	PUMP TRK. MILES		14.07
		RECEIVED	
		DEC 04 2001	
	PLUGS		
	SALES TAX	KCC WICHITA	1710.15
	TOTAL		3161.78

T. D. CSG. SET AT VOLUME

SIZE HOLE TBG SET AT 250' VOLUME

MAX. PRESS. SIZE PIPE 2 3/8

PLUG DEPTH PKER DEPTH

PLUG USED TIME FINISHED 12:00 PM

REMARKS: Ran 232' 2 3/8 DOWN BACKSIDE. MIXED AND PUMPED 280 SX 60/40 4% GEL CIRCULATED CEMENT TO SURFACE. PULLED PIPE DAN 250' 2 3/8 TDSIDE 4 1/2 MIXED AND PUMPED 99 SX 60/40 4% GEL CIRCULATED CEMENT TO SURFACE. PULLED PIPE AND TOPPED OFF WITH 10 SX 60/40 4%.

EQUIPMENT USED

NAME UNIT NO. NAME UNIT NO.

ROB P-15

GREG B-1 AND B-7

#91

CEMENTER OR TREATER

OWNER'S REP.