


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County, Sec. 23 Twp. 18 Rge. 21 (E) (W) W

Location as "NE/CNW/SW" or footage from lines c NE NE

Lease Owner Kern-Landes Explor. Co. Inc.

Lease Name Gish Well No. 1

Office Address P. O. Box 699, Magnolia, Arkansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 25 19 63

Application for plugging filed October 25 19 63

Application for plugging approved October 25 19 63

Plugging commenced October 25 19 63

Plugging completed October 25 19 63

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	248'	8 5/8"	248'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set Plug @ 550' / 20 sacks cement
Plug @ 180' / 20 sacks cement & 1/4 sack hulls
Plug @ 35' / 10 sacks cement & 1/4 sack hulls

RECEIVED
STATE CORPORATION COMMISSION
NOV 13 1963
11-13-63
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Hellar Drilling Company, Inc.
Address 1014 Union Center, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
D.L. Hellar, Pres. of Hellar Drlg. Co. Inc.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar, Pres.
1014 Union Center, Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 11th day of November, 19 63

My commission expires March 25, 1964
Catherine Darcey - Notary Public.

15-135 19104-0000

DRILLER'S LOG

COMPANY: Kern-Landes Exploration Co. Inc.
 CONTRACTOR: Hellar Drilling Company, Inc.
 LEASE: #1 Gish
 LOCATION: c NE NE Sec. 23-18-21W, Ness County, Kansas
 COMMENCED: October 15, 1963
 COMPLETED: October 25, 1963
 CASING: Set 8 5/8" surface casing @ 248' / 175 sacks cement

Dry & Abandoned

0-248	Post rock-sand-shale
248-750	Red Beds-sand
750-1030	Cedar Hills sand
1030-1343	Sand-shale-shells
1343-1375	anhydrite
1375-1515	Shale & Lime
1515-1754	Lime & shale
1754-1999	Shale & shells
1999-2012	Cimm. Anhydrite
2012-2104	Shale & shells
2104-2312	Lime & shale
2312-2415	Shale & Lime
2415-2525	Lime & shale
2525-2616	Lime
2616-2720	Lime & shale
2720-2905	Shale & Lime
2905-3020	Lime & shale
3020-3260	Shale & Lime
3260-3400	Lime & shale
3400-3790	Lime (Lsg. -K.C.)
3790-3849	Lsg. -K.C.
3849-3927	Lime
3927-4005	Lime & Shale
4005-4055	Shale & Lime
4055-4078	Lime
4078-4088	#1 Core
4088-4103	Lime
4103-4118	#2 Core
4118-4173	Lime & shale
4173-4178	Mississippian (chert)
4178-4193	Cherty Lime
4193-4207	#3 Core
4207	Rotary Total Depth
	Dry & Abandoned

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 13 1963
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Gish, located in c NE NE Sec. 23-18-21W, Ness County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By D. L. Hellar
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 11th day of November, 1963.

Catherine Dacey
 Notary Public - Catherine Dacey

My Commission Expires:
 March 25, 1964.