

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barber

County, Sec. 36 Twp. 32S Rge. (E) 15(W)

Location as "NE/CNW&SW&" or footage from lines C NE/4 NW/4

Lease Owner Beacon Resources Corporation - John C. Graves

Lease Name Carr Well No. 2

Office Address Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 11 19 69

Application for plugging filed " 19

Application for plugging approved " 19

Plugging commenced " 19

Plugging completed " 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph J. Warren

Producing formation Depth to top Bottom Total Depth of Well 4385 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 1/2" x 288'		
				STATE CORPORATION COMMISSION		
				12-16-69		
				DEC 16 1969		
				CONSERVATION DIVISION		
				Wichita, Kansas		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 285', 1/2 sack hulls, plug,
25 sacks cement. Mud to 40', 1/2 sack
hulls, plug, 10 sacks cement. 2 sacks
cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
Address 505 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
John C. Graves

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

505 Union Center, Wichita, Kansas

(Address)

Subscribed and Sworn to before me this 15th day of December 19 69

My commission expires July 28, 1970

Mary Ann Scott
Mary Ann Scott

Notary Public.

ROTARY DRILLERS' LOG

OPERATOR: Beacon Resources-John C. Graves DRILLING COMMENCED: 12/3/69
 Union Center Bldg.
 Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: 12/11/69
 505 Union Center
 Wichita, Kansas

CASING RECORD: 8 5/8" surface casing, set LOCATION: Carr #2
 at 287', with 250 sacks of C NE/4 NW/4 Sec. 36-32S-15W
 cement. Barber County, Kansas

0	-	575	Sod, sand & red bed
575	-	1510	Red bed & shale
1510	-	1828	Shale & shells
1828	-	2515	Lime & shale
2515	-	2650	Lime & shale, with chert
2650	-	2725	Lime
2725	-	4302	Shale & lime
4302	-	4337	Lime
4337	-	4358	Lime & shale
4358	-	4385	Lime
4385	-		Total Depth D & A

I hereby certify the foregoing statements to be true and correct,
 to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John C. Graves

STATE of KANSAS)
 SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 17th day
 of December, 1969.

My commission expires: July 28, 1970

Mary Ann Scott
 Mary Ann Scott, Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 12-18-69
 DEC 18 1969
 CONSERVATION DIVISION
 Wichita, Kansas