

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County. Sec. 36 Twp. 32 Rge. 15 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

NW SE NW
Lease Owner Gemini Oil Company
Lease Name Carr Well No. 2

Office Address 1408 Philtower Bldg., Tulsa, OK 74103

Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed September 12, 19 80

Application for plugging filed Verbal Application 19

Application for plugging approved Verbal Approval 19

Plugging commenced September 12, 19 80

Plugging completed September 12, 19 80

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Ownen

Producing formation Depth to top Bottom Total Depth of Well 3,700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	302'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 3,700 ft. (rotary total depth) to 300 ft. Set plug at 300 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 300 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 10 sacks cement in rat hole, 5 sacks cement in mouse hole and 5 sacks cement in water well.

Plugging operations accomplished Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Dean Britting, Agent

I, the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water #10, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 1980

Elsie Willison
Notary Public.

commission expires July 25, 1982

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1980
9-29-80
CONSERVATION DIVISION
Wichita, Kansas



