


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Barber County, Sec. 14 Twp. 32 Rge. 15 (E) (W)  
Location as "NE/CNW/SE/SW" or footage from lines C SW NE  
Lease Owner Aylward Drilling Company  
Lease Name Skinner Z#1 Well No.  
Office Address Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced 3/13/72 19  
Plugging completed 3/16/72 19  
Reason for abandonment of well or producing formation depleted.  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Biberstein  
Producing formation Depth to top Bottom Total Depth of Well 5070 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	272	none
				5 1/2"	5069	3703'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded hole to 4980' and set 5 sacks of cement. Loaded casing with water, rigged up on 5 1/2", shot pipe at 4138', 4040', 3940', 3910', 3798', 3700', pulled 114 joints. Set rock bridge at 250' and ran 4 yards of ready mix. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 21 1972  
4-21-72  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of March, 19 72

Margaret Melcher  
Notary Public.

My commission expires  
MARGARET MELCHER  
NOTARY PUBLIC  
Rice County, Kansas  
My Commission Expires  
Feb. 15, 1975

SKINNER: "Z" #1

Casing Record:      Company: Aylward Drilling Company et al      Location: C SW NE  
 Contractor: Aylward Drilling Company      Sec. 14-32-15W  
 8 5/8" - 272'      Commenced: February 21, 1965      Barber County  
 5 1/2" - 5069'      Completed: March 12, 1965      Kansas  
 Elevation: 2020 K.B.

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Soil	0	30	Set 8 5/8" surface pipe @ 272'
Gravel & Clay Streaks	30	80	w/225 sacks cement.
Red Bed	80	630	
Red Rock & Red Bed	630	940	Geological Tops:
Shale	940	1590	Heebner 4107
Anhydrite & Shale	1590	1760	Toronto 4117
Shale & Lime	1760	2590	Douglas Shale 4134
Lime	2590	2750	Douglas Sand 4187
Lime & Shale	2750	3405	Lansing 4268
Shale & Lime Streaks	3405	3510	Kansas City 4479
Shale & Lime	3510	4010	Base/Kansas City 4706
Shale & Lime Streaks	4010	4075	Marmaton 4715
Lime	4075	4078	Choteau Lime 4879
Shale	4078	4093	Kinderhook 4916
Shale w/Lime	4093	4120	Maquoketa 4950
Shale	4120	4269	Simpson 5065
Lime	4269	4348	
Chalk	4348	4363	
Lime	4363	4413	DST 4717-40 Open 1 hr. GTS/2"
Lime w/Shale Breaks	4413	4469	Gauge 519 MCF
Lime	4469	4706	Rec. 5' mud
Shale & Lime	4706	4769	BHP 1723#/30"-1696#/30"
Lime	4769	4917	FP 99-91#
Lime & Shale	4917	4980	
Lime	4980	5065	DST 4745-4815 Open 1 hr.
Sand	5065	5070 T.D.	Rec. 5' mud

RECEIVED  
 STATE COMMISSION  
 MAR 2 2 1965  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

REMARKS Cont'd

DST 5060-70 Open 1 hr.  
 Rec. 2200' gas in pipe, 60' OCM,  
 90' OCMW, 320' S1.OCW, 400' water  
 BHP 1528#/30"-1405#/30"  
 FP 83-416#

Set 5 1/2" casing @ 5069' w/150 sacks.

DST 4955-90 Open 1 hr. GTS/2"  
 Gauge 652 MCF/2", 439 MCF/10-40",  
 416 MCF/50". Rec. 245' mud.  
 BHP 1634#/30"-1510#/30"  
 FP 91-141#.

DST 4990-5005 Open 1 hr. GTS/3",  
 Gauge 439 MCF/3", 310 MCF/5", 169 MCF/15"  
 Flowed oil in 17", Approx. 30 BO/20"  
 No Water.  
 BHP 1678#/30"-1652#/30"  
 FP 1108-1239#

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Frank Hamlin

Subscribed and sworn to before me this 15th day of March, 1965

Duane Jessup  
 DUANE JESSUP Notary Public

My commission expires December 11, 1965