

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 1 Twp. 33S Rge. 13W (E) (W)

Location as "NE/CNW&SW¼" or footage from lines C N/2 N/2 NW

Lease Owner Skelly Oil Company

Lease Name G. S. Lonker Well No. 5

Office Address 212 Wolcott Building, Hutchinson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 4-29-63 19

Application for plugging filed 4-29-63 19

Application for plugging approved 4-29-63 19


Plugging commenced 4-29-63 19

Plugging completed 4-29-63 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4585' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	475'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cement plug @ 4437' - 4465' with 40 sacks cement

Plug @ 240' with 20 sacks cement

Mud to 40' Plug with 1/4 sack hulls and 10 sacks Cement  
(2 sacks in rat hole)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 6 1963

5-6-63

CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.

Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of May, 1963

My commission expires April 1, 1967

Ulanda Nichols Notary Public.



DRILLER'S LOG

COMPANY: Skelly Oil Company  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: G. S. Lonker #5  
 LOCATION: C N/2 N/2 NW Sec. 1-33S-13W  
 BARBER COUNTY, KANSAS  
 COMMENCED: 4-15-63  
 COMPLETED: 4-29-63

0	90	Surface Clay, Redbed
90	130	Redbed
130	440	Shale, Shells
440	470	Shells, Shale
470	475	Lime
475	640	Shells, Shale
640	1100	Redbed, Shale
1100	1400	Shale with Lime Streaks
1400	1880	Shale, Lime
1880	2345	Lime, Shale
2345	2515	Shale, Lime
2515	2640	Lime, Shale
2640	2890	Shale, Lime
2890	3685	Lime, Shale
3685	3871	Shale, Lime
3871	4020	Lime, Shale
4020	4090	Lime
4090	4154	Lime, Chalk
4154	4585	Lime
	<u>4585</u>	<u>Rotary Total Depth - D. &amp; A.</u>

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 MAY 6 1963  
 5-6-63  
 CONSERVATION DIVISION  
 Wichita, Kansas

Set 8 5/8" surface casing @ 475' Cemented with 140 sacks Posmix with HA5 and 135 sacks Common with HA5 and Cemented with 15 sacks Common with HA5.

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the G. S. Lonker #5, located Center of the North half of the North half of the Northwest of Section 1, Township 33 South, Range 13 West, Barber County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS }  
 COUNTY OF BARTON } SS

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 3rd day of May, 1963.

Ulanda Nichols  
 Ulanda Nichols, Notary Public

My Commission Expires:  
 April 1, 1967