

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-077-20,861-0000

LEASE NAME McDaniel

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

2310 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 9 TWP. 32 RGE. 9 (E) or (W)

LEASE OPERATOR Edmiston Oil Co., Inc.

ADDRESS 125 N. Market, Suite 1260 Wichita, KS 67202-1774

COUNTY Harper

PHONE#(316) 265-5241 OPERATORS LICENSE NO. 5042

Date Well Completed 12/21/82

Character of Well Oil

Plugging Commenced 7/11/90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 7/12/90

The plugging proposal was approved on July 10, 1990 (date)

by Agent in Dodge City, Kansas (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippi Depth to Top 4328 Bottom 4332 T.D. 4390

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-------------|---------|------|----|-------|--------|------------|
| Mississippi | | | | 8-5/8 | 374' | -- |
| | | | | 4 1/2 | 4332' | 2705' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sand off from TD to 4278'. Set plug at 4278 w/4 sx common cement, shot casing at 2705', set plug at 1300' w/25 sx, set plug at 905' w/25 sx; plugged from 374' to surface with 150 sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Edmiston Oil Co., Inc. License No. 5042

Address 125 N. Market, Suite Wichita, KS 67202-1774

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: As Above

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jon M. Callen (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein stated and the log of the above-described well as filed that the same are true and correct.

(Signature) Jon M. Callen


(Address) 125 N. Market, Suite 1260 Wichita, KS

RECEIVED
 AUG 22 1990
 8-22-90

SUBSCRIBED AND SWORN to before me this 20th day of August, 19 90

CONSERVATION DIVISION
 Wichita, Kansas

Julianne Carter
 Notary Public



My Commission Expires: November 5, 1990