

15-877-00232-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Harper County, Sec. 9 Twp. 32 Rge. 9 (E) W (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NW  
Lease Owner Mull Drilling Co.  
Lease Name Harper Coryell Well No. 1  
Office Address Wichita, Kans.  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 19  
Application for plugging filed Feb 12 19 58  
Application for plugging approved Feb 18 19 58  
Plugging commenced Feb 12 19 58  
Plugging completed Feb 17 19 58  
Reason for abandonment of well or producing formation Water

If a producing well is abandoned, date of last production X 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampell  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	160'	none
				5 1/2	4355'	3296'

Describe in-detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug back with sand from 4355' to 4300' mixed and dumped 5 sx cem from 4300' to 4260', pulled 5 1/2 csg, plug surface with pump truck, (Gloge Cem Co.) mix and pumped in 25 sx gel mud put in plug mixed and pumped in 75 sx cem., shut in with top of cem at base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 18 1958  
4-18-58  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Southwest Casing Pulling co.  
Address Great Bend, Kans.

STATE OF Kansas, COUNTY OF Sedgewick, ss.  
D. G. Comstock (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. G. Comstock  
Address

SUBSCRIBED AND SWORN to before me this 17th day of April, 1958, 19

My commission expires January 28, 1961.  
Ethel Zimmerman Notary Public.

PLUGGING  
FILE SEC. 9 T. 32R. 9W  
BOOK PAGE 82 LINE 26

ROTARY DRILLERS LOG

COMPANY : Mull Drilling Company, Inc. ROTARY DRILLING COMMENCED: 11-10-56  
Wichita, Kansas

CONTRACTOR : Mull Drilling Company, Inc. ROTARY DRILLING COMPLETED: 11-23-56  
Wichita, Kansas

CASING RECORD : Set 8 5/8" @ 120' cemented with 100 sacks cement.  
Set 5 1/2" @ 4355' cemented with 150 sacks cement.

LOCATION: CORYELL #1  
C SW/4 NW/4 of Sec. 9-32-9W  
Harper County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

Red Rock	120	Lime & Shale	3435
Red Bed	600	Lime, Shale & Sand	3641
Shale & Shells	1350	Lime & Shale	3940
Lime	1410	Lime	4230
Lime & Shale	1690	Lime & Shale	4312
Lime	1930	Lime (Mississippi)	4355 R.T.D.

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

BY J. A. Mull, Jr., PRESIDENT  
J. A. MULL, JR.

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

Subscribed and sworn to before me this 26th day of November, 1956.



Ethel Zimmerman  
NOTARY PUBLIC

MY COMMISSION EXPIRES: JANUARY 28, 1957.

STATE COMMISSION  
2-12-58

PLUGGING	
FILE	SEC. 9 T. 32R. 9.4
BOOK	PAGE 82 LINE 26