

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Barber County, Sec. 23 Twp. 32 Rge. (E) 13 (W)

Location as "NE/CNW%SW%" or footage from lines C - SW/4 SW/4 NE/4

Lease Owner Lion Oil Company

Lease Name Brooks and Younger Well No. 2

Office Address P. O. Box 639, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 9 19 55

Application for plugging filed (Verbal) July 9 19 55

Application for plugging approved (Verbal) July 9 19 55

Plugging commenced July 9 19 55

Plugging completed July 9 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4757 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	362'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud from 4757 feet to 368 feet.
Bottom plug set at 368 feet with 1/3 sack of hulls and 20 sacks of cement.
Heavy mud from 368 feet to 35 feet.
Set top plug at 35 feet with 1/2 sack of hulls and filled up with 10 sacks of cement.

Name of Plugging Contractor ~~Braham-Messman-Rinehart~~ Drilling Company (License No. 20)
Address 1005 East Second, Wichita, Kansas

STATE OF KANSAS COUNTY OF PRATT
Vernon Hayes (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Vernon Hayes*
P. O. Box 639, Pratt, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of July 19 55

My commission expires August 29, 1955

RECEIVED
STATE CORPORATION COMMISSION
JUL 27 1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 23 T 32 R 13W
BOOK PAGE 33 LINE 1

NO. 2 BROOKS-YOUNGER

WELL RECORD

Location: SW SW NE, 23-32S-13W
Barber County, Kansas

Commenced: June 24, 1955

Operator: Lion Oil Company
211 W-K-H Building, Wichita, Kansas

Completed: July 9, 1955

Contractor: Graham-Messman-Rinehart Drilling Co.
1005 East Second, Wichita, Kansas

Elevation: 1650 KB

Production: D&A

Casing Record: 8 5/8" @ 362' w/275 sacks cement

.....L O G.....

Surface Soil-Clay	50
Red Bed-Gyp	375
Shale-Red Bed	816
Shale	1673
Shale-Lime	2126
Lime-Shale	2340
Shale-Lime	3220
Lime-Shale	3960
Lime	4391
Lime-Shale	4420
Lime	4423
Coring Lime	4488
Lime	4608
Lime-Shale	4748
Viola	4757 R.T.D.

The undersigned, GRAHAM-MESSMAN-RINEHART DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART DRILLING COMPANY

By: Roger L. Messman
Roger L. Messman

Subscribed and sworn to before me
this 25th day of July, 1955.

Quantia L. Jovia
Notary Public

My Commission Expires: November 5, 1958

