

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Barber County, Sec. 23 Twp. 32 Rge. 13 (W)

Location as "NE/CNW/SW" or footage from lines C-SW/4 SW/4 NW/4

Lease Owner Monsanto Chemical Company

Lease Name Brooks and Younger Well No. 3

Office Address P. O. Box 639, Pratt, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 15 19 55

Application for plugging filed November 15 19 55

Application for plugging approved (Verbal) November 15 19 55

Plugging commenced November 15 19 55

Plugging completed November 15 19 55

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4500 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	368'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud from 4500' to 350'. Bottom plug set at 350' with 1/4 sack of hulls and 20 sacks of cement. Heavy mud to 35'. Set top plug at 35' with 1/2 sack of hulls and 10 sacks of cement on top of plug.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graham-Messman-Rinehart Drilling Company (License No. 20)

Address 1005 East Second, Wichita, Kansas

STATE OF KANSAS, COUNTY OF PRATT, ss. J. B. Gibbs

(employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

P. O. Box 639, Pratt, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of November, 19 55

commission expires September 19, 1959

[Signature] Notary Public.

PLUGGING  
FILE SEC 23 T 32 R 13W  
BOOK PAGE 16 LINE 42

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 17 1955  
CONSERVATION DIVISION  
Wichita, Kansas

NO. 3 BROOKS-YOUNGER

WELL RECORD

Location: SW SW NW, 23-32S-13W  
Harber County, Kansas

Commenced: October 31, 1955

Completed: November 15, 1955

Operator: Monsanto Chemical Company,  
Lion Oil Company Division  
211 U-K-H Building, Wichita, Kansas

Elevation: 1489 KB

Production: D&A

Contractor: Graham-Messman-Rinehart Oil Company  
1005 East Second, Wichita, Kansas

Casing Record: 8 5/8" @ 366' w/275 sacks cement

.....L O O.....

Clay-Sand-Red Bed	245
Shale-Gyp	520
Shale-Shells	1060
Shale-Lime	1595
Lime-Shale	2112
Shale-Lime	2270
Lime-Shale	2355
Shale-Lime	2505
Lime-Shale Streaks	2619
Shale-Lime	3365
Lime-Shale	3545
Shale-Lime	3695
Lime-Shale	3776
Shale-Lime	3850
Lime-Shale	4090
Lime	4375
Coring Mississippi	4410
Misc. Lime-Chert	4444
Misc	4492
Lime	4500 R.T.D.

The undersigned, GRAHAM-MESSMAN-RINEHART OIL COMPANY, hereby certifies that the above log is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MESSMAN-RINEHART OIL COMPANY

By: J. A. Gilliland  
J. A. Gilliland

Subscribed and sworn to before me  
this 18th day of November 1955.

Jacqueline L. Lewis  
Notary Public

My Commission Expires: November 5, 1958

STATE OF KANSAS  
JAN 14 1956  
COMMISSIONER OF GEOL. & MINES  
DIVISION

PLUGGING  
NW SEC 23 T 32 R 13W  
RAC 16 LINE 42