


15-077-00830-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Harper County, Sec. 8 Twp. 32 Rge. 9 (E) (W) X

Location as "NE/CNWSW" or footage from lines SE SE NW

Lease Owner Mull Drilling Company, Inc.

Lease Name Easterby Well No. 1

Office Address Box 349 Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 4-27-70 19

Application for plugging approved 4-28-70 19

Plugging commenced 6-6-70 19

Plugging completed 6-13-70 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 4361 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	200	None
				4 1/2	4361	3854.10

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved unit into location.

Plugged bottom back to 4300' with sand and dumped 3 sacks of cement on bottom with dump bailer. Rigged up jacks, worked casing, had 35" tension at 1600 psi or 69,000 lbs.

Shot pipe at 3895'.
Pulled a total of 123 joints of 4 1/2" casing.

Loaded up trailer. Set plug at 190', dumped 10' rock bridge. Tore down pole and moved off location.

Plugged hole with 3 yards of ready mix cement.

RECEIVED
STATE CORPORATION COMMISSION
6-19-70
JUN 19 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold

P. O. Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18 day of June, 1970

My commission expires



Notary Public.

15-077-00830-0000

Rotary Driller's Log

Company: Mull Drilling Co., Inc.
Wichita, Kansas

Rotary Drilling Commenced: 10-12-59

Contractor: Mull Drilling Co., Inc.
Wichita, Kansas

Rotary Drilling Completed: 10-25-59

Casing Record: Set 8 5/8" @ 200' w/125 sax cmt.
Set 4 1/2" @ 4361' w/100 sax cmt.

Location: Easterby No. 1
SE SE NW
8-32S-9W
Harper County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

290'	Red Bed
1140'	Shale & Shells
1490'	Shale
1579'	Shale & Lime
1690'	Lime w/Shale
1935'	Lime
3090'	Lime & Shale
3651'	Sandy Lime & Shale
4010'	Lime & Shale
4124'	Lime
4159'	Lime w/Shale
4210'	Lime
4341'	Lime w/Shale
4361'	Mississippi Chert & Total Depth

RECEIVED
STATE CORPORATION COMMISSION
4-30-70
APR 30 1970
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

Mull Drilling Co., Inc.

R. James Gear

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn before me this 2nd day of November, 1959.

Madge M.

My Commission Expires: February 24, 1960