

15-165-30110-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Rec'd - 1983
07-06-1983

Give All Information Completely
Make Required Affidavit

COUNTY Rush SEC. 20 TWP. 16S RGE. 17W E/W
Location as in quarters or footage from lines:
SW SW SW

Lease Owner Frontier Oil Co.
Lease Name Urban "C" #1 Well No. 1
Office Address 1720 Kansas St. Bk. Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed 12-17-65
Application for plugging filed 6-14-83
Plugging commenced 6-15-83
Plugging completed 6-15-83
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well B. E. Beck
Producing formation Toronto Depth to top 3248' bottom 3254' T.D. RTD--3538'
Show depth and thickness of all water, oil and gas formations. Plug @3270'

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
	135 sax	0'	216'	8 5/8"	11-15-65	Still in hole
	275 sax	0'	3515'	4 1/2"	11-25-65	Still in hole
	Set stage collar @ 1148' with 550 sax				11-25-65	Still in hole

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set. Allied Cementing, Russell, plugged well with pump truck

The following are the materials used, starting with what was put in the hole first:
Pumped 20 sax 50-50 pozmix, 6% gel and 1/2 sax hulls @ 3260'.
Pulled tubing to 1150'.
Pumped 100 sax 50-50 pozmix, 6% gel and 1 1/2 sax hulls @ 1150' and hole loaded.
Pulled tubing and filled hole with same pozmix, hole stayed full.
Pumped 5 sax 50-50 pozmix, 6% gel down the 8 5/8" surface pipe and shut in @ 500PSI.

(Plugs calculated by displacement).

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allied Cementing, Russell, Ks. 67665

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jean Angle (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Jean Angle
1720 Kansas State Bank Bldg, Wichita.
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of July, 1983

Stella Sewell
Notary Public.

My Commission expires: June 24, 1984



