

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33526
Name: Stucky, Kenneth R. Oil & Gas Operator
Address 1: P.O. Box 576
Address 2: _____
City: Burrton State: KS Zip: 67020 + _____
Contact Person: Kenneth Stucky
Phone: (620) 463-7624
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Miss Depth to Top: 3200 Bottom: 3402 T.D. 3300
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-079-20653-00-00
Spot Description: _____
SE SW NW Sec. 3 Twp. 23 S. R. 3 East West
3,230 Feet from North / South Line of Section
4,200 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Harvey
Lease Name: Schrag J Well #: 1
Date Well Completed: 03/21/1997
The plugging proposal was approved on: 04/02/2013 (Date)
by: B J Hope (KCC District Agent's Name)
Plugging Commenced: 04/03/2013
Plugging Completed: 04/03/2013

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Mississippi	gas	Surface	8.625	250	0
		Production	4.5	3402	1700

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sanded back to 3170. Capped W/ 4 sks cement on top. Cut production casing off at 1700 ft. and pulled out of hole. TIHW tubing to 500' Pumped 35 sks hot plug of class A common W/ 3 % CC. Wait 1 hr. and ran sandline and tagged plug @ 400'. Pulled tubing up to 300' and ran 5 sks of gel. Pumped 80 sks of class a common. Pulled all the tubing out of the hole. Topped off surface casing with 10 sks. Checked plug on 04/04/13. Plug at surface.

Plugging Contractor License #: 33948 Name: Worx LLC
Address 1: P.O. Box 242 Address 2: _____
City: Hillsboro State: KS Zip: 67063 + _____
Phone: (620) 382-7635
Name of Party Responsible for Plugging Fees: Kenneth R Stucky
State of Kansas County, Harvey, ss.
Kenneth R Stucky Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Kenneth R Stucky

RECEIVED
KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

OCT 16 2013

CONSERVATION DIVISION
WICHITA, KS

