

15-13530152-0000


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Ness County, Sec. 27 Twp. 18S Rge. 21 (E) (W) X

Location as "NE/CNW/SW" or footage from lines C NE NW

Lease Owner Pickrell Drilling Company

Lease Name Pfaff Well No. H-1

Office Address 705 Fourth National Bank Building Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 1-13-66 19

Application for plugging approved 1-14-66 19

Plugging commenced 5-17-66 19

Plugging completed 5-20-66 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey

Producing formation Depth to top Bottom Total Depth of Well PB 4182 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	315	None
				5 1/2	None	2179

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved in. Cleaned out cellar. Dumped 5 sacks of cement at 3200'. Working pipe. Cut off casing head. Welded on 8 5/8 collar. Shut off water.

Working pipe. Spudding out bridge at 2300'. Shot pipe at 2700'.

Working pipe. Spudding bridge at 1850'. Shot pipe at 2160'. Pulling pipe.

Squeezed well with 20 sacks of mud and 125 sacks of cement by Globe Oil Well Cementing, Inc.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 24 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.

Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of May, 19 66

My commission expires May 27, 1969

Notary Public.

**ROTARY DRILLING LOG**

*File Copy*

15-138-30152-0000

*Copy to SCC 6-9-66*

COMPANY: PICKRELL DRILLING COMPANY  
705 4th National Bank Bldg.  
Wichita, Kansas

Rotary Drilling Commenced 9--7-65

Rotary Drilling Completed 9-18-65

LOCATION: PFAFF "H" No. 1, C NE NW Section 27-18-21W, Ness County, Kansas.

CONTRACTOR: PICKRELL DRILLING COMPANY  
Wichita, Kansas

CASING RECORD: (15 jts) 8 5/8" surface casing, 315', set with 175 sacks cement.  
Circulated. (134 jts) 5 1/2" casing set at 4213 with 75 sacks cement.  
Completed 7:30 A.M. September 19, 1965.

**LOG**

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

70	Top Soil & Sand	<u>C. F. S.</u>
530	Shale & Shells	4105
740	Shale, Shells & Red Bed	4115
775	Shale & Shells	4125
980	Sand	4141
1285	Shale, Shells & Red Bed	4147
1335	Red Beds	4155
1370	Anhydrite	4160
1376	Shale & Shells	4167
1800	Shale	4173
2025	Shale & Shells	4178
2350	Shale & Lime	4183
2710	Lime	4191
3477	Lime & Shale	4195
3540	Sandy Lime & Shale	4202
3670	Shale & Lime	4212
3950	Lime	
4020	Lime & Shale	
4055	Lime with some cherty	<u>Slope Tests</u>
4080	Ft. Scott	1600
4098	Cherokee	2750
4105	Lime & Shale	3680
4141	Lime, Shale & Sand	4125
4155	Sand	
4163	Shale, Sand, Lime & Chert	<u>S. L. M.</u>
4212	Mississippian - RTD	2252
		3178
		4054

RECEIVED  
STATE GEOLOGICAL COMMISSION  
JUN 10 1966  
CONSERVATION DIVISION  
Wichita, Kansas


The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By [Signature]  
C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 27th day of September, 1965, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.



My commission expires: June 21, 1966

Maxine Blackman  
Maxine Blackman, Notary Public