

15.35.001800000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make/Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Ness County. Sec. 25 Twp. 18 Rge. (E) 21 (W)

Location as "NE/CNW/SW" or footage from lines NW SE

Lease Owner R. W. Shields

Lease Name Ryersee Well No. 1

Office Address 308 Rule Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 4, 1960

Application for plugging filed April 4, 1960

Application for plugging approved April 4, 1960

Plugging commenced April 4, 1960

Plugging completed April 4, 1960

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert P. Leiker, Victoria, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4270 Feet

Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	345	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1/3 Sack Hulls and Wooden Plug Set @ 550°
Mixed 20 Sacks Cement through the drill pipe

1/3 Sack Hulls and Wooden Plug set @ 180°
Mixed 15 Sacks Cement through the drill pipe

1/3 Sack Hulls and Wooden Plug set @ 40°
Mixed 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1960
4-8-60
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

Address P. O. Box 97, Great Bend, Kansas.

STATE OF Kansas, COUNTY OF Barton, ss.

V. Richard Hoover (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover


P. O. Box 97, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 5th day of April, 19 60

My commission expires May 19, 1962

Norris Taylor
Norris Taylor Notary Public.



15:135 00180-0002

WELL LOG

R. W. Shields
308 Rule Building
Wichita, Kansas

Ryersee No. 1
NW SE of Section 25-18S-21W
Ness County, Kansas

Contractor: Chief Drilling Co., Inc.
Rotary: 0 - 4270*

Commenced: 3-23-60
Completed: 4-4-60
D & A

Casing Record: 8 5/8" set @ 345° with 225 sacks cement, cement circulated.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Clay, shale and post rock	0	130	2162 Gr.
Shale and shells	130	410	2164 D. F.
Sand	410	445	2166 K. B.
Clay and shells	445	625	
Red bed, shale, sand streaks	625	835	
Sand	835	1075	
Shale	1075	1395	
Anhydrite	1395	1420	
Shale and shells	1420	2115	
Lime and shale	2115	2555	
Lime	2555	2845	
Shale and lime	2845	3295	
Shale	3295	3335	
Lime	3335	3635	
Lime and shale	3635	3680	
Lime	3680	4125	
Shale & sand streaks	4125	4225	
Chert	4225	4270	
Total Depth	4270		

<u>FORMATION TOPS</u>	
Anhydrite	1395 (≠ 771)
Heebner	3635 (-1469)
Lansing-Kansas City	3679 (-1513)
Cherokee Shale	4126 (-1960)
Mississippi	4226 (-2060)
Total Depth	4270 (-2104)

RECEIVED
STATE CORPORATION COMMISSION

APR 8 1960


STATE OF KANSAS)
 SS
COUNTY OF BARTON)

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NW SE of Section 25-18S-21W, Ness County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.
V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 6th day of April, 1960



My commission expires: May 19, 1962.

Norris Taylor
Norris Taylor, Notary Public