


15-077-00170-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Harper County, Sec. 14 Twp. 32S Rge. 9W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Ctr. SE/4, SE/4, NW/4

Lease Owner R. C. Patton Co., & Others.

Lease Name Beiberstine Well No. 1

Office Address 612 Orpheum Bldg. Wichita 2, Kansas.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 21st, 19 50

Application for plugging filed January 26th, 19 50

Application for plugging approved January 26th, 19 50

Plugging commenced January 27th, 19 50

Plugging completed February 1st, 19 50

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 5040 Feet

Show depth and thickness of all water, oil and gas formations:

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	200Ft.	None
				5 1/2"	4484Ft.	3600Ft.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with Heavy Mud to 4461Ft, this is up to float collar, from 4461Ft. to 4405 Ft. with Rock and 6 Sacks Cement, then with heavy Mud to 200Ft. the Rock Bridge and 15 Sacks Cement, then with heavy mud to 15 Ft. below cellar, then 5 Sacks cement to top of Surface Casing.

RECEIVED
Conservation Div.
2-3-50
FEB 3 1950
STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to R. C. Patton Co.,
Address 612 Orpheum Bldg. Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgewick, ss.
R. C. Patton (employee of owner) OR (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God:

(Signature) R. C. Patton

612 Orpheum Bldg. Wichita 2, Kansas. (Address)

SUBSCRIBED AND SWORN to before me this 3rd day of February, 19 50

[Signature]
Notary Public

My commission expires Oct 4th, 1952

22-5133-s 9-48-10M

PLUGGING
FILE SEC-14T32R9W
BOOK PAGE 137 LINE 13

15-077-00170-0000

R. C. Patton Co., & Others.
Biberstein Well # 1
Total Depth 5040ft.
Comm. 12/13/49
Comp. 1/20/50
Contractor R. C. Patton Co.,

Location Ctr. SE/4, SE/4, NW/4, Section
14-T32S-R9W Harper Co., Kansas.
CASING RECORD
8 5/8" Casing at 200ft.
Cemented with 125 Sacks Cement.
5 1/2" O. D. Casing at 4484ft.
Cemented with 125 Sacks Cement.

Clay & Sand	25
Red Beds	215
Shells & Red Bed	320
Red Bed	460
Shale & Shells	1355
Lime & Shale	1560
Shale & Shells	1680
Lime	1830
Shale	1860
Shale & Lime	1945
Lime	2020
Lime & Shale	2375
Shale Shells	2480
Lime & Shale	3035
Shale	3100
Lime Broken	3120
Lime & Shale	3284
Lime	3300
Lime & Shale	3445
Sandy Lime	3464
Lime & Shale	3506
Shale	3542
Sand Douglas	3576
Shale	3717
Sandy Lime	3810
Lime	3955
Lime & Shale	3956
Lime	3967
Lime & Shale	3993
Lime	4153
Shale & Lime	4397
Shale	4415
Lime Cherty	4560
Lime	4578
Lime Shale	4636
Lime	4752
Shale	4756
Lime & Shale	4791
Shale	4815
Shale & Cherty Lime	4850
Snad Shale	4885
Sand	4890
Shale	4941
Shale Sand & Shells	4958
Sandy Shale	4988
Lime	5040
Total Depth	5040

TOPS	
Heebner Shale	3402
Oread Lime Base	3471
Douglas Formation	3471
Douglas Sand	3542
Stalnaker Sand	3717
Lansing Lime Base	3874
K.C. Lime	3959
Mississippi	4412
Kinderhook Shale	4653
Chattanooga Shale	4770
Simpson Sand	4816
Arbuckle Lime	4985
No Viola Lime	
No Maquoketa	

RECEIVED

Conservation Div.

FEB 3 X 1950

STATE CORPORATION
COMMISSION
KANSAS

STATE OF Kansas COUNTY OF Sedgwick ss.

I, the undersigned, being duly sworn, on oath state that the above statement and log is a true and correct record and log of the well drilled at the location above described.

PLUGGING
 FILE SEC 14 T 37 R 9 W
 BOOK PAGE 137 LINE 13

R. C. PATTON CO.,

By R. C. Patton

Subscribed and sworn to before me this 3rd day of February, 1950

J. P. Kendrick
Notary Public.

My Commission expires Oct 4th, 1952