

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec. 14 Twp. 32 Rge. 9 (E) (W)

Location as "NE/CNW/SE" or footage from lines C SW NE

Lease Own: Anadarko Production Company

Lease Name Black "A" Well No. 1

Office Address P.O. Box 351, Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 7-29 19 64

Application for plugging filed 7-21 19 64

Application for plugging approved 7-23 19 64


Plugging commenced 7-29 19 64

Plugging completed 7-29 19 64

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well A. Elving

Producing formation Depth to top Bottom Total Depth of Well 4507 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	314'	6
				4 1/2	4506'	3995

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted 5 sxs cmt. on B.P. @ 4290', filled hole with mud rock bridge at 275'.  
Spotted 35 sxs, filled hole with mud to 41', formed rock bridge. Spotted 10 sxs to surface, capped.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 4 1964  
8-4-64  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Sargent's Casing Pulling Service  
Address 1546 Clay Court, Liberal, Kansas

STATE OF KANSAS, COUNTY OF SEWARD, ss.  
S. H. Neithercoat, Supt. Drlg. & Prod. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. H. Neithercoat

P.O. Box 351, Liberal, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July 19 64

Donald L. Vangieson Notary Public

My commission expires

MY COMMISSION EXPIRES SEPT. 29, 1964

15-077-00273-0000

DRILLER'S LOG

WELL NAME Black "A" #1

COMPANY OPERATING Anadarko Production Company  
 ADDRESS of COMPANY Box 351, Liberal, Kansas

WELL LOCATION C 1/2 SW 1/2 NE 1/2,  
660 ft. North of South line,  
660 ft. East of West line; Sec. 14 Twp. 32 Rge. 9, Harper County, Kansas

DRILLING STARTED 6-25, 1964  
 WELL COMPLETED 7-29, 1964

DRILLING COMPLETED 7-10, 1964  
 WELL CONNECTED \_\_\_\_\_, 19\_\_\_\_

ELEVATION 1500 ft. Ground Level CHARACTER OF WELL (Oil, Gas, or Dry Hole) Dry Hole

OIL OR GAS SANDS OR ZONES - PERFORATIONS - ACIDIZING AND FRACTURING INFORMATION					
Name	From	To	No. of Shots	Gallons Used	Kind Used
Mississippian	4409	4474	10	250	BDS
				3500	5% gelled acid

CASING RECORD

Size	Amount Set	Sacks of Cement	Amount Pulled
8 5/8	314	225	6
4 1/2	4506	100	3995

FORMATION RECORD

Formation	Top	Bottom	Formation	Top	Bottom
Red Bed & Shells	0	317			
Shale & Shells	317	1350			
Lime & Shale	1350	3540			
Sand	3540	3565			
Lime & Shale	3565	3675			
Shale & Sand	3675	3808			
Lime	3808	4507			
Total Depth	4507				

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 8-4-64  
 AUG 4 1964  
 CONSERVATION DIVISION  
 Wichita, Kansas

RESULTS of INITIAL PRODUCTION TEST: \_\_\_\_\_