

15-077-00827-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Harper County, Sec. 4 Twp. 32s Rge. 9w (E) (W)
Location as "NE/CNW/SW" or footage from lines C W/2 SW SW
Lease Owner Santa-Fe Pipe & Supply, Inc.,
Lease Name Weathered Well No. 1
Office Address Box 562, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) gas
Date well completed October 3 19 57
Application for plugging filed November 5 19 66
Application for plugging approved November 7 19 66
Plugging commenced November 18 19 66
Plugging completed November 22 19 66
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Archie Elving
Producing formation Depth to top Bottom Total Depth of Well 4410' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	160'	none
				5-1/2"	4400.36'	3737.43'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4410' - 4365' - plug
4365' - 4270' - sand
4270' - 4230' - 5 sacks cement
4230' - 180' - mud
180' - 170' - rock bridge
170' - 95' - 25 sacks cement
95' - 40' - mud
40' - 30' - rock bridge
30' - base - 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1966
12-12-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Santa-Fe Pipe & Supply, Inc.,
Address Box 562, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
T. L. Nutt (Employer or owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt
Box 562, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of December, 19 66

Mary M. Guenier
Notary Public.

My commission expires July 31, 1970

FILE COPY
 15-077-00827-0000
ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company
 Wichita, Kansas

Rotary Drilling Commenced 9/18/57

LOCATION: CW/2 SW SW Sec. 4-32-⁹, Harper County, Kansas

Rotary Drilling Completed 10/3/57

Weathered #1

CONTRACTOR: PICKRELL DRILLING COMPANY
 Wichita, Kansas

CASING RECORD: 4 jts. 160' 8 5/8" Spiralweld Casing cemented with 135 sacks cement circulated.

140 jts. 5 1/2" 14# J-55 Seamless Casing set at 4403' cemented with 75 sacks cement.

LOG

(Figures indicate bottom of formation - measurements from top of rotary bushing.)

Red Rock	160	Circ. for samples at	4300
Red Bed & Shale	660		4310
Shale & Shells	890		4320
Salt & Shale Shells	1370		4332
Lime & Shale	1560		4345
Lime	1975		4360
Lime & Shale	2700		4370
Lime	2900		4410
Shale & Sand	3075		
Sandy Lime	3200		
Lime	3270		
Lime & Shale	3580		
Lime	4299		
Mississippi	4410 T.D.		

S.L. M. at 2000 - O.K.
 3000 - "
 4000 - "

Slope Test at 2000 0° off
 3000 0° off
 4000 0° off

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 12 1966
 12-12-66
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitt, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By C. W. Sebitt
 Attorney-in-Fact

STATE OF KANSAS, }
 COUNTY OF SEDGWICK } ss.:

On this 17th day of October, 1957, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitt, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: July 30, 1958

Bartholomew H. Stebbins
 Notary Public