


15-077-00110-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Harper County, Sec. 4 Twp. 32 Rge. 9 (W) SW NE  
Location as "NE/CNW/SW" or footage from lines  
Lease Owner Santa-Fe Pipe & Supply, Inc.,  
Lease Name Simpson Well No. 1  
Office Address Box 562, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) gas  
Date well completed December 2 19 58  
Application for plugging filed November 5 19 66  
Application for plugging approved November 7 19 66  
Plugging commenced November 14 19 66  
Plugging completed November 18 19 66  
Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Archie Elving  
Producing formation Depth to top Bottom Total Depth of Well 4455' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	205'	none
				4-1/2"	4451.33'	3777.08'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4455' - 4418' - plug  
 4418' - 4325' - sand  
 4325' - 4289' - 3 sacks cement  
 4289' - 200' - mud  
 200' - 190' - rock bridge  
 190' - 115' - 25 sacks cement  
 115' - 40' - mud  
 40' - 30' - rock bridge  
 30' - base - 10 sacks cement


RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 12 1966  
 12-12-66  
 CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Santa Fe-Pipe & Supply, Inc.,  
Address Box 562, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.  
T. L. Nutt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt  
Box 562, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of December, 1966  
July 31, 1970  
Mary M. Guenier  
Notary Public.



15-877-00110-0000

ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company

Rotary Drilling Commenced 11-17-58

LOCATION: C-SW NE Sec. 4-32S-9W  
Harper County, Kansas  
#1 Simpson

Rotary Drilling Completed 12-2-58

CONTRACTOR: **PICKRELL DRILLING COMPANY**  
Wichita, Kansas

CASING RECORD: 200' (5 jts.) 8-5/8" OD Spiralweld 22.7# Casing, cemented with 100 sacks common cement with 2% Gel. Cement circulated.

4-1/2" casing set at 4454' with 110 sacks cement.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Shale & surface sand	34'	Circ. for samples at	4365'
Sand & Gravel	50'		4375'
Red Bed	200'		4382'
Red Rock & Shale	780'		4390'
Shale & Lime	1565'		4400'
Lime	2020'		4410'
Lime & Shale	3135'		4430'
Lime	3210'		4455'
Lime & Shale	3285'		
Lime, Sand & Shale	3505'		
Lime & Shale	3519'		
Lime, Shale & Sand	3675'		
Lime	3870'		
Lime & Shale	3955'		
Lime	4203'		
Lime & Shale	4355'		
Mississippi	4455'	T.D.	

S.L.M. at 2000 - O.K.  
3000 - O.K.  
4000 - O.K.

Slope Test at 2000 0° off  
3000 0° off  
4000 0° off

**RECEIVED**  
STATE CORPORATION COMMISSION  
DEC 12 1966  
12-12-66  
CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY  
By [Signature]  
Attorney-in-Fact

STATE OF KANSAS }  
COUNTY OF SEDGWICK } ss.:

On this 6 th day of December, 19 58, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: May 13, 1962

[Signature]  
Notary Public  
(Mary Ellen Sampson)