

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barber County, Sec. 23 Twp. 32S Rge. 15 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
SW SW NW

Lease Owner Raymond Oil Company, Inc.
Lease Name Swayden Well No. 1


Office Address One Main Place, Suite 900, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole

Date Well completed February 20 19 81
Application for plugging filed February 20 19 81
Application for plugging approved February 20 19 81
Plugging commenced February 20 19 81
Plugging completed February 20 19 81
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. V. Leslie
Producing formation Depth to top Bottom Total Depth of Well 3650'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	251'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

Pumped 40 sacks cement through drill pipe to 250'. Pushed bridge, hulls & plug to 40' with 10
sacks cement. Plugged rat hole with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc. 3-9-81
CONSERVATION DIVISION

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Betty Brandt (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Betty Brandt
910 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of February, 1981

Rebecca L. Matthews
Notary Public.

My commission expires May 17, 1983



R O T A R Y D R I L L E R S ' L O G

OPERATOR: Raymond Oil Co., Inc.
One Main Place, Suite 900
Wichita, Kansas 67202

DRILLING COMMENCED: February 14, 1981

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: February 20, 1981

CASING RECORD: 6 Jts. 251' of new 8-5/8"
cemented with 220 sacks.

LOCATION: Swayden No. 1
SW SW NW
Section 23-32S-15W
Barber County, Kansas

0 - 40	Sand
40 - 251	Red bed
251 - 981	Red bed & shale
981 - 3010	Shale & lime
3010 - 3181	Red bed & shale
3181 - 3621	Shale & lime
3621 - 3650	Lime & shale
3650	Rotary Total Depth

RECEIVED
 MAR - 9 1981
 3-9-81
 COMPTROLLER DIVISION
 Kansas Geological Survey

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

Copy sent to:
State Corporation Commission
Kansas Geological Society
Kansas Geological Survey

GRAVES DRILLING CO., INC.

By Rebecca L. Matthews
Secretary-Treasurer

STATE OF KANSAS)
) ss:
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, this 25th day of February, 1981.

Rebecca L. Matthews
Rebecca L. Matthews Notary Public

My commission expires: May 17, 1983.