

15-007-01452-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit.
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 19 Twp. 32 Rge. 15W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW NW
Lease Owner Time Petroleum Company
Lease Name R. I. Dee Geer Well No. 1
Office Address 815 Union Nat'l Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed October 17, 1961
Application for plugging filed November 11, 1961
Application for plugging approved November 11, 1961
Plugging commenced November 11, 1961
Plugging completed November 11, 1961
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred W. Hampel
Producing formation Depth to top Bottom Total Depth of Well 4840' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	986	
				4 1/2"	4839	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

T. D. 4840' - S. P. 8 5/8" 986' CWC 100 sacks cement.
4 1/2" 4839' - 125 sacks cement. Top Perf. 4772'-4777'
Bottom sand to 4750' - add 5 sacks cement - pulled pipe
mud to 300' set R. B.
10' R. B. - 300' - 20 sacks cement
R. B. - 35' - 10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1966
3-1-66
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Smith & Smith Pipe Pulling
Address Cushing, Oklahoma

STATE OF Kansas COUNTY OF Sedgewick ss.
Max W. Satterthwaite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Max W. Satterthwaite
815 Union National Bldg
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28 day of February 1966

My commission expires August 6, 1969

Josephine Danner
Notary Public.

WELL LOG

COMPANY TIME PETROLEUM, COMPANY

SEC. 19 T. 32S R. 15W

FARM DeGEER NO. 1

LOC. C-NW/4


TOTAL DEPTH 4840'

COUNTY BARBER CO., KANSAS

COMM. October 2, 1961 COMP. October 17, 1961

CONTRACTOR GARVEY DRILLING COMPANY

CASING 8-5/8" @ 986' w/300 sax.
4 1/2" @ 4839' w/150 sax.



ELEVATION 1850' DF

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

45	Surface sand & red bed
289	Red bed
800	Red bed & shale
986	Red bed
1973	Shale & shells
2240	Shale & lime
2475	Lime & shale
2915	Lime
3040	Lime & shale
3650	Shale & lime
3740	Lime & shale
3875	Shale, sand & lime
4055	Lime
4165	Shale & lime
4755	Lime
4840	Cherty lime
4840	T. D.

RECEIVED
STATE CORPORATION COMMISSION

FEB 14 1963
2-14-63
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of BARTON } ss

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #1 DeGEER well.

Verne A. Morris

Subscribed and sworn to before me this 24th day of October 1961

My Commission Expires: November 12, 1962

Banfubing
NOTARY PUBLIC