

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-21527-0000

LEASE NAME Marsh Ranch

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2

1980 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 19 TWP. 32 SRGE. 15 (X) or (W)

COUNTY Barber

Date Well Completed 1/83

Plugging Commenced 5-20-87

Plugging Completed 6-23-87

LEASE OPERATOR Gore Oil Company

ADDRESS 125 N. Market, Suite 1750

Wichita, KS 67202

PHONE# (316) 263-3535 OPERATORS LICENSE NO. 5552

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 1 - Dodge City

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippi Depth to Top 4770 Bottom 4780 T.D. 4838

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi	Oil, Gas, Wtr	0	323	8 5/8	311	0
		0	4836	4 1/2	4826	2250

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Dump sand to 4628. Dump 5 sx Common cement. Shoot off and pull 4 1/2" casing. Pump down 8 5/8" casing; 3 sx Hulls, 15 sx Gel, 50 sx 60/40, 10 sx Gel, 1 sx Hulls, wiper plug, 100 sx 60/40. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 7718

Address Pratt, KS

STATE OF Kansas COUNTY OF Sedgwick, ss.


Scott W Scheuerman (Employee of Operator) ~~xxxxxx~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Scott W Scheuerman

(Address) 125 N. Market, Suite 1750  
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 24th day of June, 1987

Rebecca K. Crawford  
Rebecca K. Crawford Notary Public  
STATE CORPORATION COMMISSION



JUN 25 1987  
6-25-87  
Form CP-4  
Revised 08-84  
CONSERVATION DIVISION  
Wichita, Kansas